



QUOTATION

DATE - 12/7/2023 –
QUOTE - #081023-001

FROM – Chuck Hundley-C-770-328-0847
E-MAIL – chundley@sseteam.com

PROJECT:

LOCATION:

Exchange Park	Decatur, GA
---------------	-------------

QUOTE CONTACT INFORMATION:

Contact Name	Nick Jovene	Contact Phone Number	970-227-2814
Contact Company	CGL	Contact E-Mail	njovene@cglcompanies.com

QUOTATION SPECIFICS:

Specification Section	NONE	Freight	Included
Product	Focus Gym Flooring	Installation	Included
Manufacture	Connor Sports	Tax @ 8%	Included
Approval Status	NONE	ADDENDUMS NOTED	NONE

BID PRICE:

--

**PRICING BELOW INCLUDES REMOVAL AND DISPOSAL OF EXISTING WOOD FLOOR AND
 INSTALL OF NEW FLOOR on or Around 60% of existing Floor,**

Quoting approximately (4524 sq. ft) of “Focus” Gymnasium wood floor by Connor Sports. Floor system features a pre-assembled subfloor system with solid blocking, anchor pins, anchor clips and “continuous focus pads”. System height 1-3/4” using 25/32” X 2-1/4” wide 2nd or better grade Maple, Repaint Game Lines and Center Logo.

Sourcewell Contract # 031022-GER

Contingency (Per Owner’s Discretion)	\$11,705.00
All Material and Labor	\$117,055.00
Total	\$128,760.00

*****Quote is valid through 3/29/24.**

LEAD TIME – approximately 8-10 weeks after receipt of official PO.

General Notes:

Sales/Use taxes are INCLUDED in above bid amount.
 Payment and Performance Bonds are NOT INCLUDED in the above price. Add 1% for our standard bond form. If alternate bond forms are required there may be an additional cost and the forms will be subject to approval by our bonding company.
 Materials stored at owner or GC’s request will incur storage fees and handling charges.
 All electrical service requirements, including conduit, wiring and/or final hook which may be required shall be provided by electrical subcontractor.
 Hoisting for non-ground floor access, unless specifically indicated above is not included.
 Permits, if required, are not included and shall be provided by others at others expense.



Flooring -- Concrete slab must be level to 1/8" in a 10' radius and dry to 4.5# per 1,000 Sq.Ft. as tested by Calcium Chloride dry crystal testing methods. All slab prep work, including leveling, and associated cost is by others. Moisture test results must be provided to SSE prior to scheduling of crew to jobsite by others and at others expense. Thresholds, reducers, base and removal/reinstallation of anything on the floor (i.e. bleachers or floor inserts) which may be required are excluded unless specifically included above.

For Wood flooring contracts only; GC shall provide subcontractor with electrical service for floor sanders – 208 v./3phase/100 amps.