### **Agenda Item**

File ID: Z-20-1243876 Substitute Agenda Date July 14, 2020

**Public Hearing: YES ⊠ NO □ Department:** Planning and Sustainability

**SUBJECT:** 

**Commission District(s):** 4 & 6

Application of John Corcoran to rezone properties from R-75 (Residential Medium Lot-75) to HR-2 (High Density Residential-2) District to allow for the construction of up to 250 residential units consisting senior housing and market rate residences at 3383, 3393, and 3391 Kensington Road and 4150 and 4200 Memorial Drive.

Petition No.: Z-20-1243876

**Proposed Use:** Multi-family and Senior Housing

Location: 3383, 3393 & 3391 Kensington Road; and 4150 and 4200 Memorial Drive

Parcel No.: 15-250-06-009, 15-251-03-001, 15-251-03-002, 15-251-03-003, 15 251 03 004

**Information Contact:** Jahnee Prince, AICP

**Phone Number:** 404-371-2607

### **PURPOSE:**

Application of John Corcoran to rezone properties from R-75 (Residential Medium Lot-75) to HR-2 (High Density Residential-2) District to allow for the construction of up to 250 residential units consisting of senior housing and market rate residences. The property is located on the south side of Kensington Road and the west side of Memorial Drive, at 3383, 3393, and 3391 Kensington Road; and 4150 and 4200 Memorial Drive in Decatur, Georgia. The property has approximately 580 feet of frontage along Kensington Road, 845 feet of frontage along Memorial Drive and contains 4.76 acres.

### **RECOMMENDATION:**

**COMMUNITY COUNCIL:** Full Cycle Deferral

**PLANNING COMMISSION:** Deferral

**STAFF RECOMMENDATION:** Approval with Conditions

PLANNING STAFF ANALYSIS: The applicant was originally requesting to rezone to the MU-4 (Mixed Use High Density) District which allows residential densities up to 40 dwelling units per acre. The project was initially proposing up to 170 affordable senior housing residences within two four-story multi-family buildings at a density of 40 units per acre, but was not able to provide a minimum of 20% nonresidential uses as required by the MU-4 zoning. The application was deferred from the June 9, 2020 Board of Commissioners meeting to the July 14<sup>th</sup> Board of Commissioners meeting to allow the applicant time to revise their application to the HR-2 (High Density Residential-2) District to allow an increase in residential density from 40 to 52 dwelling units per acre (consisting of 130 senior housing units and 120 market rate multi-family units) and increase the building height from four stories to five stories to be more consistent with the higher densities called for by the Regional Center (RC) character area of the 2035 Comprehensive Plan (up to 120 dwelling units per acre). The HR-2 zoning (with conditions) allows the applicant to provide some accessory and primary nonresidential uses consistent with the

mixed-use goals of the Regional Center Character Area of the Comprehensive Plan and the goals of the 2003 and 2012 Kensington LCI *Small Area Plans*. While there is no requirement for non-residential uses in the HR-2 zoning district, 10.6% of the total building square footage is proposed for non-residential use. The submitted concept plan, along with zoning conditions recommended by Planning Department Staff, is consistent with the Kensington LCI goals and TOD (Transit Oriented Development) guidelines adopted by MARTA focusing on high density, pedestrian focused developments by bringing the buildings up to wide sidewalks along the street, locating parking behind the buildings, and providing public access to open space. Additionally, the HR-2 district is more consistent with the adjacent HR-3 zoning to the west. With the recommended transportation improvements by Planning Department staff, the rezoning proposal should not cause an excessive or burdensome use of existing streets and transportation facilities. Therefore, Staff is recommending approval of the HR-2 zoning subject to Staff's recommended conditions.

**PLANNING COMMISSION VOTE: Deferral 8-0-0.** L. Osler moved, A. Atkins seconded for a Deferral to the July 14, 2020 Board of Commissioners agenda.

COMMUNITY COUNCIL VOTE/RECOMMENDATION: Full Cycle Deferral 9-0-1. The Council recommended "Full Cycle Deferral" since the proposed concept plans were in the process of being redesigned and Council wanted to review plans when they were completed. There was additional discussion concerning that there was not enough parking, and concerns that seniors who would live in the development would have no cars and no nearby parks, grocery stores, or drug stores to walk to.

# SUBSTITUTE AGENDA ITEM PAGE SUBSITUTE CONDITIONS Z-20-1243876 July 10, 2020

- 1. The 4.76 acre tract (the "Project Site") shall be developed in general conformity with the conceptual plan entitled "Exhibit A" and entitled Kensington Pointe and dated June 29, 2020 by the Department of Planning and Sustainability. Development shall comply with the intent of MARTA Transit-Oriented Development (TOD) Guidelines by moving the buildings close to the Kensington Road and Memorial Drive rights-of-way with parking located behind the proposed buildings. Building height shall be five stories for the residential buildings and a minimum of thirty feet tall for the office building. Density will be between 40 and 60 dwelling units per acre. Internal sidewalks (minimum 5 feet in width) shall be constructed adjacent to all buildings, connected throughout the entire Project Site to provide for continuous connectivity to all buildings and open space to proposed sidewalks along Kensington Road and Memorial Drive. If the sidewalks crosses a driveway, it shall be clearly marked with striping, pavers, or raised crosswalks. The Developer shall install pet refuse stations at appropriate locations along internal sidewalks/walking trails.
- 2. A commercial or office building shall be located on the northeast corner of the site at the Kensington Road/Memorial Drive intersection. Non-residential uses shall constitute a minimum of 10% of the total building square footage on the project site. Reserved space without immediate tenant for future occupancy shall count toward compliance with this condition. Nonresidential uses may also include a fitness center, a business center, recreation center, and/or community rooms.
- 3. Open space shall comprise a minimum of 15% of the project site. Provide and maintain outdoor play and recreation areas with a minimum area of five (5) percent of the total area of the lot or four thousand (4,000) square feet, whichever is greater. The applicant will meet the minimum and is currently estimated at 30% open space.
- 4. Building materials to comply with Article 5 of the Zoning Ordinance. No vinyl or metal buildings are allowed. The building elevations for Kensington Roads shall be reasonably consistent to the elevations submitted on July 9, 2020 to the Planning Department. The final building elevations and building materials shall be approved in writing by the District and Super District Commissioners for the Project Site prior to the issuance of the Building Permit for the Project Site. Final building elevations shall show articulation of different building materials.
- 5. All openings of the parking deck facing the internal street shall be treated with a mural, architectural elements, trellis with vines, or a combination thereof. All internal elements to the parking deck such as plumbing pipes, fans, ducts and lighting shall be concealed from the exterior view. Lighting shall be shielded to minimize light spillover beyond and above the deck. The lighting on top deck shall be fully shielded fixtures and directed towards the parking spaces and not to any adjacent properties.

- 6. One blade sign not to exceed 60 square feet per side with approximate dimensions of 3 feet wide x 20 feet tall shall be permitted for each residential building. One wall mounted sign not to exceed 6 feet tall x 10 feet wide for the office/commercial building may be erected. One monument sign not to exceed 20 square feet (per sign face) shall be allowed at the intersection of Memorial Drive and the internal private service road. One wall mounted sign not to exceed 10 square feet may be erected at the intersection of Kensington Road and the private internal service drive. Wayfaring signs of less than 18 inches in height shall also be permitted. All of these sign conditions shall be subject to the requirements of the DeKalb County Sign Ordinance. If there is a conflict between these conditions and the DeKalb County Sign Ordinance, the more restrictive requirement shall apply.
- 7. Prior to the issuance of a Land Development Permit for the Project Site, the developer, in cooperation with the abutting LDG development, shall submit to the DeKalb County Transportation Department a Pedestrian Safety Analysis prepared by a professional transportation engineer for safe pedestrian access from the Project Site to the Kensington MARTA station.
- 8. In order to match the streetscape standards that are required of the abutting LDG Development on Kensington Road to the greatest extent possible, a streetscape zone shall be constructed along Kensington Road and shall include the installation of landscape strips and street trees consistent with those on the LDG site as approved by the County Arborist, with a minimum 10-foot wide sidewalk and a minimum 10-foot wide green space/landscape strip except in front of the office/commercial building where existing right-of-way is enlarged. Under no circumstance shall the landscape strip be less than 5-feet wide. The Landscape strip shall be between the curb and the sidewalk. Lighting shall be placed within the landscape strip. A pedestrian pocket park with a seating area shall be provided along the western portion of the project site between the proposed buildings and the abutting LDG Development site.
- 9. A streetscape zone shall be established along the Memorial Drive frontage to the extent possible given project design constraints, topographical issues, and Georgia Department of Transportation (GDOT) requirements. The existing sidewalk shall be retained and repaired to ADA standards if damaged and extended to meet the new sidewalk along Kensington if necessary. Between the sidewalk and the building edge along Memorial Drive, the applicant shall provide a minimum 5-foot wide and a maximum 10-foot wide landscape strip. This landscaping may consist of small trees and /or hedges. The existing decorative street lighting will be inspected and repaired if necessary.
- 10. A landscape plan showing the proposed landscaping within the streetscape zones along Kensington Road and Memorial Drive, along the proposed internal private drive, and for any open space area on the project site shall be approved in writing by the District and Super District Commissioners for the Project Site prior to the issuance of the Building Permit for the Project Site.
- 11. Refuse areas shall not be visible from the public street and shall be fenced or screened with a combination of materials and colors to match building materials of the primary building.
- 12. All equipment located on any flat top roof shall be screened from view.
- 13. All storm water detention shall be underground.

### **DeKalb County Department of Planning & Sustainability**

### 330 Ponce De Leon Avenue, Suite 500 Decatur, GA 30030

(404) 371-2155 / plandev@dekalbcountyga.gov

Planning Commission Hearing Date: June 2, 2020 6:30 P.M. Board of Commissioners Hearing Date: July 14, 2020 9:00 A.M.

### **SUBSTITUTE**

	SIAFF AI	NALYSIS_		
Case No.:	Z-20-1243876		Agenda #: N.1	
Location/Address:	3383, 3391, & 3393 Kensington F and 4150 and 4200 Memorial Dr Decatur, Georgia.		Commission Distr	ict: <b>4</b> Super District: <b>6</b>
Parcel ID(s):	15 250 06 009, 15 251 03 001, 15 251 03 002, 15 251 03 003, 15 03 004	5 251		
Request:	To rezone properties from R-75 (Res Residential -2) District to allow up to market rate units.		•	. –
Property Owner(s):	MARTA			
Applicant/Agent:	John Corcoran			
Acreage:	4.76 acres			
Existing Land Use:	Parking Lot			
<b>Surrounding Properties:</b>	Kensington MARTA station to the the east: the DeKalb County Juve and vacant land and offices to the	enile Detention		
Adjacent Zoning:	North: R-75 South: C-1 East: C	)-I & HR-3 <b>Wes</b>	t: HR-3 and Avono	dale Estates
Comprehensive Plan:	RC (Regional Center)/Kensington	LCI X Co	onsistent	Not Consistent
Proposed Density: N.	A	Existing De	ensity: NA	
•	are Footage: Up to 250 multi- or housing residences and 120	Existing U	nits: NA (Parking I	Lot)
Proposed Lot Coverag	ge: NA	Existing Lo	ot Coverage: NA	

### **Zoning History:**

The properties appear to have been zoned R-75 since adoption to the first zoning ordinance and map in 1956.

### **Project Analysis:**

The subject properties comprise 4.76 acres and contain a MARTA parking lot. The property is part of a triangle of land bounded on the north by Kensington Road, on the southeast by Memorial Drive, and on the southwest by Covington Highway. In addition to two vacant properties, the other land uses in this triangle are the DeKalb Juvenile Justice Center and a Citgo gas station. The Kensington MARTA Station is located across Kensington Road to the north. A sidewalk is located along Kensington Road, next to the curb.

The applicant was originally requesting to rezone to the MU-4 (Mixed Use High Density) District which allows residential densities up to 40 dwelling units per acre. Under that MU-4 zoning the project was proposing up to 170 senior housing residences within two four-story multi-family buildings at a density of 40 units per acre. All of those proposed units were to be affordable housing units. However, the application was deferred from the June 9, 2020 Board of Commissioners meeting to the July 14<sup>th</sup> Board of Commissioners meeting to allow the applicant time to revise their application to HR-2 (High Density Residential-2) zoning to allow an increase in residential density from 40 to 52 dwelling units per acre and increase the building height from four stories to five stories. The higher densities allowed by HR-2 zoning (up to 60 units per acre) are more consistent with the Regional Center (RC) character area of the 2035 Comprehensive Plan calling for up to 120 dwelling units per acre and the Transit Oriented Development (TOD Guidelines) adopted by MARTA in 2010 to provide a high density, pedestrian-focused development near the Kensington MARTA station. The HR-2 district is also more be consistent with the adjacent HR-3 zoning to the west. The applicant is applying for tax credits from the Georgia Department of Community Affairs, and in order for their tax credit application to remain competitive, the applicant must have a rezoning request approved by July 31<sup>st</sup>.

The proposed site plan and application is in keeping with the Transit Oriented Development (TOD) Guidelines adopted by MARTA in 2010 to provide a high density, pedestrian-focused development near public transit stations by bringing the buildings up to the street and proposed wide sidewalks, locating parking behind the buildings, and providing publicly accessible open space. The submitted application indicates five-story buildings will be located adjacent to the proposed sidewalk and right-of-way along Kensington Road and Memorial Drive, with parking and an internal private access drive located behind the buildings. Access is proposed via one driveway off Kensington Road and a right in, right out access off Memorial Drive. 250 residential units are proposed at a density of 52 dwelling units per acre, with 130 of those units dedicated for affordable senior housing and 120 units will be market rate multi-family. The project's total residential building square footage is 319,840 square feet which includes senior housing units and market rate multi-family units. While no non-residential uses are required in HR-2 zoning, the applicant is providing 10.6% of the project site as office space (38,032 square feet), consistent with the 10% non-residential uses required in the adjacent HR-3 multi-family project abutting the north property line. Providing a commercial component is consistent with the Kennsington LCI and MARTA TOD design guidelines to provide a mixture of land uses around the MARTA station to encourage pedestrian activity and reduce automobile dependency. The applicant indicates that the proposed building materials will likely consist of fiber cement and masonry veneers.

A four-story parking deck containing 340 parking spaces is proposed behind the five-story buildings. Since the project is within 1000 feet of a MARTA station, the zoning ordinance allows a 25% parking reduction upon application of an administrative variance, which would require only 265 parking spaces. Therefore the proposed number of parking spaces complies with code requirements. The project is providing an abundance of open space (37% open space provided, 15% required by the zoning ordinance) and outdoor recreation areas (10,367 s.f. required by zoning ordinance, 23,509 s.f. provided) located throughout the project site and will consist of passive open space which will be accessible to the public via internal sidewalks within the project site that connect to proposed public sidewalks along Kensington Road and Memorial Drive. Due to the pedestrian-focused design, the generous amount of open space and outdoor play area provided, and topographical constraints of the subject properties, the applicant indicates

that administrative variances may be needed for a portion of the streetscape requirements of the zoning ordinance (10-foot wide sidewalk, 10-ft wide landscape strip, street trees 40 feet on center, etc) along Kennsington Road and Memorial Drive.

### **Compliance with District Standards:**

HR-2 STANDARD	REQUIRED/ALLOWED	PROVIDED/PROPOSED	COMPLIANCE
MAX. D.U.s/ACRE (BASE, W/BONUSES)	Base: 40 d.u.s/ac W/Bonuses: 60 d.u.s/ac.	52 units/acre; Proximity to MARTA = 100% density bonus = 40 bonus units	Yes
MIN. OPEN SPACE	15%	37%	Yes
MIN. LOT AREA	12,500 s.f.	187,308 s,f,	Yes
MIN. LOT WIDTH	100 ft.	845 feet (Memorial Dr)	Yes
MIN. TRANSITIONAL BUFFER	None Required (abuts HR-3 zoned properties)	20 foot buffer abutting HR- 3 zoning to the north	Yes
FRONT SETBACK (For entire bldg. site)	Min 10 ft, Max 20 feet	10 feet	Yes
REAR SETBACK	20 ft.	20 feet	Yes
MINIMUM UNIT SIZE	650 s.f.	745 s.f.	Yes
MAX. BLDG. HEIGHT	8 stories or 100 ft	5 stories	Yes
TRANS'L HEIGHT PLANE	Applicable on north side abutting Kensington Road	Applicant indicates will comply.	Yes
OUTDOOR PLAY AREA	Min. area of 5% of total lot area or 4,000 s.f., whichever is greater 5% of lot area = 10,367 s.f.	23,509 s.f. (12.8%)	Yes

PARKING	Min. – Senior Housing5 spaces per dwelling unit, plus .25 spaces per du for guest parking (98 spaces) Multi-Family—1.5 spaces per unit (180 spaces) Office—1 space per 500 s.f. (76 spaces) TOTAL REQUIRED = 354 parking spaces TOTAL REQUIRED with 25% admin. variance for being within 1000 feet of MARTA transit station = 265 parking spaces		Yes with admin. variance (within 1000 ft of MARTA station)
SIDEWALKS AND STREETSCAPING		Project will attempt to fully comply but may need some variances.	Undetermined. Project may need administrative variances

Surrounding Development. There is new market-rate senior housing multi-family development construction underway along Mountain Drive around ¾ mile distance from the subject property to the north on the other side of the MARTA station (the Avondale Hills and Avondale Park developments). These developments are geographically separated from the subject parcels by the MARTA station and roadways to the immediate north. The properties to the west currently contain vacant land and offices. These properties were recently rezoned to HR-3 (High Density Residential) District on July 24, 2019 by the Board of Commissioners and approved for 244 apartments within a six story building. The subject site backs up to the DeKalb Juvenile Justice Center to the southwest and a Shell gas station to the south. To the east across Memorial Drive are offices and vacant land.

<u>Supplemental Requirements</u>: The application indicates there will be compliance with the following Senior Housing Supplemental Regulations of the Zoning Ordinance.

Section 27-4.2.26 requires the following for Senior Housing:

- A. Primary uses: Senior housing facilities shall include either independent living units or assisted living units (confirm they are independent living units), or both. The independent living units may be either single-family (detached) residences or multifamily (attached) residences.\_
  - The primary use of the proposed development is independent senior housing.
- B. Accessory uses: Senior housing facilities shall include one (1) or more of the following accessory uses: 1. Ancillary clinics, personal service, retail (e.g., pharmacy, hair salon, medical offices). 2. Central kitchen and dining facility. 3. Recreation and amenities. 4.

Building/Clubhouse for classes, meetings, concerts, storytelling, etc. 5. Adult day care.

Accessory uses of senior housing include a clubhouse for classes, meetings, and other community amenities.

- C. The maximum number of unrelated residents living independently (not requiring personal care) and at age fifty-five (55) or older allowed in an independent living unit is one (1) per bedroom.
  - The maximum number of unrelated residents living independently (not requiring personal care) and at age 55 or older allowed in independent living unit is one per bedroom.
- D. Height Standards: A senior living facility in which all of the occupied units are occupied by at least one senior aged fifty-five (55) or older is authorized up to ten (10) stories without a height SLUP in HR, MU3, MU-4, and MU-5 zoning districts, subject to transitional height plane regulations in Article 5.

#### The proposed building height is five stories.

E. Accessibility standards: All senior housing shall incorporate accessibility standards that meet certification requirements for Easy Living or Universal Design and/or include all of the following minimum features: 1. At least one (1) step free entrance to the main floor at either the front or side of the structure; if only one (1) is provided, it shall not be from a patio or raised deck. 2. Main floor of each unit shall include a kitchen, entertaining area, and master bedroom with full bathroom. 3. Every door on the main floor shall provide a minimum width of thirty-four (34) inches of clear passage. 4. Blocking shall be installed in the master bath around toilet, tub, and shower for placement or future placement of grab bars.

The development will incorporate all accessibility standards cited above.

F. Assisted living, nursing and continuing care facilities shall provide the following: 1. Primary and secondary support services: Approval for assisted living, nursing or continuing care facilities shall not be granted without documentation of provisions for the following primary and secondary services: a. Primary services: on-site dining facility, 24-hour on-call medical services, on-site licensed practical nurse, on-call registered nurse, linen and housekeeping services, and transportation services. b. Secondary services: physical therapy, medication administration program, care technician services (clothes changing, bathing, etc.), on-site personal care (barber, beauty salon), fitness center, library. c. Access to outdoor seating and walking areas shall be provided as part of every assisted living, nursing or continuing care facility.

This is not an assisted living facility, it is an independent living facility.

G. A senior housing facility shall only be approved after consideration of the use permit criteria, found in Article 7 and after consideration of the following: 1. Proximity and pedestrian access to retail services and public amenities. 2. Transportation alternatives. 3. Integration into existing neighborhoods through connectivity and site design. 4. Diverse housing types. 5. Site and building design that encourages social interaction. 6. Building design that meets Easy Living standards.

### All of these criteria cited above were considered.

H. In addition, in consideration of the special land use permit or special administrative permit for a senior housing facility, the following criteria shall be evaluated based on the degree to which these elements provide transition from the proposed project to adjacent existing development: 1. Building height. 2. Landscaping. 3. Maximum lot coverage. 4. Setbacks from exterior property lines. 5. Site size. 6. Access to thoroughfare.

All of these criteria cited above were considered.

I. Submittal requirements. The following documents and information are required for submittals for rezoning, special land use permits, land development permits and building permits associated with proposed senior living facilities: 1. Survey and site plan (per established requirements in Article 7). 2. Landscape and tree plan. 3. Number and location of residential units. 4. Types of units. 5. Amenities. 6. Institutional/non-residential services. 7. Proximity to services such as health care, shopping, recreation, and transit. 8. Other documents addressing the approval criteria in subsections G and H above.

All have been submitted or are addressed via proposed conditions of SLUP approval.

### **Access and Transportation Considerations**

Planning Department Staff is recommending conditions of zoning approval relating to adequate transportation infrastructure to accommodate the proposed mixed-use rezoning and senior housing project as follows:

1. Prior to the issuance of a Land Development Permit for the Project Site, the developer shall submit to the DeKalb County Transportation Department a Pedestrian Safety Analysis prepared by a professional

transportation engineer for safe pedestrian access from the Project Site to the Kensington MARTA station. The Applicant shall be required to implement the recommendations set forth in the Analysis as required by the Transportation Department.

### Sidewalk/Pedestrian Access

Based on the submitted information and field investigation of the project site, there are sidewalks along this stretch of Kensington Road and Memorial Drive within this established commercial area. Planning Department Staff is recommending as a condition of zoning approval that 10-foot wide sidewalks be installed along Kensington Road and Memorial Drive, and that 5-foot wide internal sidewalks be constructed along all buildings to be continuously connected across the project site.

#### LAND USE AND ZONING ANALYSIS

Section 27-7.3.5 of the Zoning Ordinance, "Standards and factors governing review of proposed amendments to the official zoning map" states that the following standards and factors shall govern the review of all proposed amendments to the zoning maps.

### A. Whether the zoning proposal is in conformity with the policy and intent of the comprehensive plan:

The proposed HR-2 zoning district allowing residential densities up to 60 dwelling units per acre and accessory commercial uses is consistent with the Regional Center (RC) character area of the 2035 Comprehensive Plan calling for up to 120 dwelling units per acre, and also encourages development opportunities that are consistent with the goals of the 2003 and 2012 Kensington LCI *Small Area Plans* and the Transit Oriented Development (TOD) Guidelines adopted by MARTA in 2010 to encourage "transit-oriented development" as "a high-density, mixed-use development that provides a central transit "village", and to provide pedestrian-focused development by locating buildings adjacent to wide sidewalks along the street frontage, locating parking behind the buildings, and providing publicly accessible open space.

### B. Whether the zoning proposal will permit a use that is suitable in view of the use and development of adjacent and nearby properties:

Based on the submitted information, it appears that the rezoning proposal is compatible and consistent with the nearby MARTA station, surrounding commercial and institutional uses, and other high density multi-family projects either approved or under construction in the surrounding area.

### C. Whether the property to be affected by the zoning proposal has a reasonable economic use as currently zoned:

While the properties currently have a reasonable economic use as a MARTA parking lot, the proposed high density residential zoning and senior housing development with accessory non-residential uses will better comply with the intent of the Regional Center character area's policies for high density mixed use in the area.

D. Whether the zoning proposal will adversely affect the existing use or usability of adjacent or nearby property:

It does not appear that the high density residential zoning district would adversely affect the existing mixed use development pattern in the surrounding area encompassing institutional, office, multi-family, and single-family uses. The HR-2 zoning district (allowing between 40 and 60 dwelling units per acre) is consistent with the Regional Center Character Area designation, the Kensington LCI, and the TOD guidelines. The HR-2 zoning with conditions as recommended by staff would also allow the applicant to provide some accessory and nonresidential uses to achieve the mixed-use goals of the Regional Center Character Area of the Comprehensive Plan and the MARTA TOD guidelines. Additionally, the HR-2 district is more consistent with the adjacent HR-3 zoning to the west. With the recommended transportation improvements by Planning Department staff, the rezoning proposal should not cause an excessive or burdensome use of existing streets and transportation facilities.

E. Whether there are other existing or changing conditions affecting the use and development of the property, which give supporting grounds for either approval or disapproval of the zoning proposal:

Changing conditions which provide supporting grounds for approval include several new, underconstruction and proposed multi-family developments in the nearby area, and local and regional policy discussions for expanded transit and transit-supportive funding for pedestrian infrastructure.

F. Whether the zoning proposal will adversely affect historic buildings, sites, districts, or archaeological resources:

Based on the submitted information, no historic buildings, sites, districts, or archaeological resources are located on the subject properties or in the surrounding area.

G. Whether the zoning proposal will result in a use which will or could cause an excessive or burdensome use of existing streets, transportation facilities, utilities, or schools:

Planning Department staff is recommending conditions of zoning approval relating to adequate transportation infrastructure to accommodate the proposed senior housing project. Since the proposed project is for senior housing, there will be no impacts on the school system. With recommended transportation improvements, existing streets should be adequate to accommodate the zoning proposal since the site accesses a six-lane major arterial road (Memorial Drive) and a four-lane minor arterial road (Kensington Road). The applicant will need to obtain a sewer capacity letter from the Department of Watershed Management to verify if sewer capacity is adequate.

H. Whether the zoning proposal adversely impacts the environment or surrounding natural resources:

The proposed development is not expected to have unusual impacts on the natural environment.

### **STAFF RECOMMENDATION: APPROVAL WITH CONDITIONS**

The applicant was originally requesting to rezone to the MU-4 (Mixed Use High Density) District which allows residential densities up to 40 dwelling units per acre. The project was initially proposing up to 170 affordable senior housing residences within two four-story multi-family buildings at a density of 40 units per acre, but was not able to provide a minimum of 20% nonresidential uses as required by the MU-4 zoning. The application was deferred from the June 9, 2020 Board of Commissioners meeting to the July 14<sup>th</sup> Board of Commissioners meeting

to allow the applicant time to revise their application to the HR-2 (High Density Residential-2) District to allow an increase in residential density from 40 to 52 dwelling units per acre (consisting of 130 senior housing units and 120 market rate multi-family units) and increase the building height from four stories to five stories to be more consistent with the higher densities called for by the Regional Center (RC) character area of the 2035 Comprehensive Plan (up to 120 dwelling units per acre). The HR-2 zoning (with conditions) allows the applicant to provide some accessory and primary nonresidential uses consistent with the mixed-use goals of the Regional Center Character Area of the Comprehensive Plan and the goals of the 2003 and 2012 Kensington LCI *Small Area Plans*. While there is no requirement for non-residential uses in the HR-2 zoning district, 10.6% of the total building square footage is proposed for non-residential use.

The submitted concept plan, along with zoning conditions recommended by Planning Department Staff, is consistent with the Kensington LCI goals and TOD (Transit Oriented Development) guidelines adopted by MARTA focusing on high density, pedestrian focused developments by bringing the buildings up to wide sidewalks along the street, locating parking behind the buildings, and providing public access to open space. Additionally, the HR-2 district is more consistent with the adjacent HR-3 zoning to the west. With the recommended transportation improvements by Planning Department staff, the rezoning proposal should not cause an excessive or burdensome use of existing streets and transportation facilities. Therefore, Staff is recommending approval of the HR-2 zoning subject to the following conditions:

- 1. The 4.76 acre tract (the "Project Site") shall be developed in general conformity with the conceptual plan entitled "Exhibit A" and entitled Kensington Pointe and dated June 29, 2020 by the Department of Planning and Sustainability. Development shall comply with the intent of MARTA Transit-Oriented Development (TOD) Guidelines by moving the buildings close to the Kensington Road and Memorial Drive rights-of-way with parking located behind the proposed buildings. Building height shall be five stories for the residential buildings and a minimum of thirty feet tall for the office building. Density will be between 40 and 60 dwelling units per acre. Internal sidewalks (minimum 5 feet in width) shall be constructed adjacent to all buildings, connected throughout the entire Project Site to provide for continuous connectivity to all buildings and open space to proposed sidewalks along Kensington Road and Memorial Drive. If the sidewalks crosses a driveway, it shall be clearly marked with striping, pavers, or raised crosswalks. The Developer shall install pet refuse stations at appropriate locations along internal sidewalks/walking trails.
- 2. A commercial or office building shall be located on the northeast corner of the site at the Kensington Road/Memorial Drive intersection. Non-residential uses shall constitute a minimum of 10% of the total building square footage on the project site. Reserved space without immediate tenant for future occupancy shall count toward compliance with this condition. Nonresidential uses may also include a fitness center, a business center, recreation center, and/or community rooms.
- 3. Open space shall comprise a minimum of 15% of the project site. Provide and maintain outdoor play and recreation areas with a minimum area of five (5) percent of the total area of the lot or four thousand (4,000) square feet, whichever is greater. The applicant will meet the minimum and is currently estimated at 30% open space.
- 4. Building materials to comply with Article 5 of the Zoning Ordinance. No vinyl or metal buildings are allowed. The building elevations for Kensington Roads shall be reasonably consistent to the elevations submitted on July 9, 2020 to the Planning Department. The final building elevations and building materials shall be approved in writing by the District and Super District Commissioners for the Project Site prior to the issuance of the Building Permit for the Project Site. Final building elevations shall show articulation of different building materials.

- 5. All openings of the parking deck facing the internal street shall be treated with a mural, architectural elements, trellis with vines, or a combination thereof. All internal elements to the parking deck such as plumbing pipes, fans, ducts and lighting shall be concealed from the exterior view. Lighting shall be shielded to minimize light spillover beyond and above the deck. The lighting on top deck shall be fully shielded fixtures and directed towards the parking spaces and not to any adjacent properties.
- 6. One blade sign not to exceed 60 square feet per side with approximate dimensions of 3 feet wide x 20 feet tall shall be permitted for each residential building. One wall mounted sign not to exceed 6 feet tall x 10 feet wide for the office/commercial building may be erected. One monument sign not to exceed 20 square feet (per sign face) shall be allowed at the intersection of Memorial Drive and the internal private service road. One wall mounted sign not to exceed 10 square feet may be erected at the intersection of Kensington Road and the private internal service drive. Wayfaring signs of less than 18 inches in height shall also be permitted. All of these sign conditions shall be subject to the requirements of the DeKalb County Sign Ordinance. If there is a conflict between these conditions and the DeKalb County Sign Ordinance, the more restrictive requirement shall apply.
- 7. Prior to the issuance of a Land Development Permit for the Project Site, the developer, in cooperation with the abutting LDG development, shall submit to the DeKalb County Transportation Department a Pedestrian Safety Analysis prepared by a professional transportation engineer for safe pedestrian access from the Project Site to the Kensington MARTA station.
- 8. In order to match the streetscape standards that are required of the abutting LDG Development on Kensington Road to the greatest extent possible, a streetscape zone shall be constructed along Kensington Road and shall include the installation of landscape strips and street trees consistent with those on the LDG site as approved by the County Arborist, with a minimum 10-foot wide sidewalk and a minimum 10-foot wide green space/landscape strip except in front of the office/commercial building where existing right-of-way is enlarged. Under no circumstance shall the landscape strip be less than 5-feet wide. The Landscape strip shall be between the curb and the sidewalk. Lighting shall be placed within the landscape strip. A pedestrian pocket park with a seating area shall be provided along the western portion of the project site between the proposed buildings and the abutting LDG Development site.
- 9. A streetscape zone shall be established along the Memorial Drive frontage to the extent possible given project design constraints, topographical issues, and Georgia Department of Transportation (GDOT) requirements. The existing sidewalk shall be retained and repaired to ADA standards if damaged, and extended to meet the new sidewalk along Kensington if necessary. Between the sidewalk and the building edge along Memorial Drive, the applicant shall provide a minimum 5-foot wide and a maximum 10-foot wide landscape strip. This landscaping may consist of small trees and /or hedges. The existing decorative street lighting will be inspected and repaired if necessary.
- 10. A landscape plan showing the proposed landscaping within the streetscape zones along Kensington Road and Memorial Drive, along the proposed internal private drive, and for any open space area on the project site shall be approved in writing by the District and Super District Commissioners for the Project Site prior to the issuance of the Building Permit for the Project Site.
- 11. Refuse areas shall not be visible from the public street and shall be fenced or screened with a combination of materials and colors to match building materials of the primary building.
- 12. All equipment located on any flat top roof shall be screened from view.

13. All storm water detention shall be underground.

### **Attachments:**

- 1. Department and Division Comments
- 2. Board of Health Comments
- 3. Board of Education Comments
- 4. Application
- 5. Site Plan
- 6. Zoning Map
- 7. Land Use Plan Map
- 8. Aerial Photograph
- 9. Site Photographs



### **NEXT STEPS**

If this application is approved, the following will be required:



- **Land Disturbance Permit** (Required for of new building construction on non-residential properties, or land disturbance/improvement such as storm water detention, paving, digging, or landscaping.)
- **Building Permit** (New construction or renovation of a building (interior or exterior) may require full plan submittal or other documentation. Zoning, site development, watershed and health department standards will be checked for compliance.)



- Certificate of Occupancy (Required prior to occupation of a commercial or residential space and for use of property for a business. Floor plans may be required for certain types of occupants.)
- **Plat Approval** (Required if any parcel is being subdivided, re-parceled, or combined. Issued "administratively"; no public hearing required.)
- **Sketch Plat Approval** (Required for the subdivision of property into three lots or more. Requires a public hearing by the Planning Commission.)
- Overlay Review (Required review of development and building plans for all new construction or exterior modification of building(s) located within a designated overlay district.)
- **Historic Preservation** (A Certificate of Appropriateness is required for any proposed changes to building exteriors or improvements to land when located within the Druid Hills or the Soapstone Geological Historic Districts. Historic Preservation Committee public hearing may be required.)



- Variance (Required to seek relief from any development standards of the Zoning Ordinance. A public hearing and action by the Board of Appeals are required for most variances.)
- Minor Modification (Required if there are any proposed minor changes to zoning conditions that were approved by the Board of Commissioners. The review is administrative if the changes are determined to be minor as described by Zoning Code.)
- **Major Modification** (Required submittal of a complete zoning application for a public hearing if there are any proposed major changes to zoning conditions that were approved by the Board of Commissioner for a prior rezoning.)
- **Business License** (Required for any business or non-residential enterprise operating in Unincorporated DeKalb County, including in-home occupations).
- **Alcohol License** (Required permit to sell alcohol for consumption on-site or packaged for off-site consumption. Signed and sealed distance survey is required. Background checks will be performed.)

Each of the approvals and permits listed above requires submittal of application and supporting documents, and payment of fees. Please consult with the appropriate department/division.

EXHIBIT Kennsington Pointe 06/29/20 C3-MF A1-MF AT-MF DEPARTMENT OF JUVENILE JUSTICE A1-SL PARKING DECK A1-SL OFFICE BUILDING B1-SL B1-SL 81-SL B1-SL B1-SL B1-SL A1-SL B1-SL B1-SL A1-SL A1-SL A1-SL B1-SL MEMORIAL DRIVE

ARG HOUSING DEVELOPMENT CORPORATION

KENSINGTON POINTE MULTI-USE RESIDENTIAL DEVELOPMENT

> SITE PLAN SCALE: 1" = 40'-0"

THE CORCORAN OTA GROUP ARCHITECTS





# FIBER CEMENT SIDING

### ARTISAN LAP SIDING

Thick, fiber cement lap siding elevates the aesthetic of traditional wood siding with lower maintenance.

 Widths:
 5.25"
 7.25"

 Exposure:
 4"
 6"



# REVEAL PANEL WITH SURROUND TRIM

Make a dramatic statement with exposed trim that boldly frames the smooth panels with a modern industrial look. This raised trim catches available light to give your design strong geometric definition. Reveal Surround trim is available primed or with a clear anodized finish and is compatible with either primed or ColorPlus panels.


### BRICK VENEER



FACE BRICK (FIELD COLOR)
RUNNING BOND PATTERN
QUEEN SIZE



### METAL BALCONY GUARDRAIL (BLACK)



### SOLARBAN ARCHITECTURAL GLAZING



### SAMPLE FIBER CEMENT PANELS






KENSINGTON POINTE

MULTI-USE RESIDENTIAL DEVELOPMENT

JULY 7, 2020



SITE PLAN 1" = 40'-0"





Keri Taylor-Spann < Keri.Taylor-Spann@thehdc.org>

Wed 7/1/2020 3:02 PM

To: Reid, John; Williams, Matthew C.; John Corcoran < John.Corcoran@thehdc.org>

Cc: Frank, Debbie <dfrank@itsmarta.com>; Floyd, Greg <gfloyd@itsmarta.com>; Prince, Jahnee R.; Michael Corcoran (corcoran@corcoran-ota.com)

John,

#### Please see below:

- 1. Senior Housing:
  - a. Total (5 stories): 169,655 SF
  - b. Ground Floor only: 33,931 SF
- 2. Multi-family:
  - a. Total (5 stories): 150,185 SF
  - b. Ground Floor only: 30,037 SF
- 3. Parking Deck:
  - a. Total (4 stories): 126,080 SF
  - b. Floor Plate: 31,520 SF
- 4. Office:
  - a. Total (2 stories): 38,032 SF
- 5. Area of Non-residential at ground floor:
  - a. Office: 20,48 SF
  - b. Senior Housing: 1,763 SF
  - c. Multi-family: 1,829 SF
  - d. Total non-residential at ground floor: 23,840 SF

Thank You, Keri Taylor-Spann



Keri Taylor-Spann <Keri.Taylor-Spann@thehdc.org>

Mon 6/29/2020 3:46 PM

To: Reid, John; John Corcoran < John.Corcoran@thehdc.org>
Cc: Frank, Debbie < dfrank@itsmarta.com>; Floyd, Greg < gfloyd@itsmarta.com>; Prince, Jahnee R.; Williams, Matthew C.; Michael Corcoran (corcoran@corcoran-ota.com)



Kensington Pointe\_Site Plan\_... 402 KB

Please see the attached draft site plan for the Kensington Master Development. Our presentation to the DeKalb County Board of Commissioners will include a full rendering of the attached site plan. W

Phase I – 130 unit Senior Community

Along Memorial Drive

Phase II – 120 unit Family Community

Kensington Road

ARG Office Building

Approx. 25,000+ square feet at Kensington Road and Memorial Drive

Keri Taylor-Spann



Keri Taylor-Spann < Keri.Taylor-Spann@thehdc.org > Tue 6/30/2020 5:40 PM

To: Reid, John; Williams, Matthew C.; John Corcoran < John.Corcoran@thehdc.org>

Cc: Frank, Debbie <dfrank@itsmarta.com>; Floyd, Greg <gfloyd@itsmarta.com>; Prince, Jahnee R.; Michael Corcoran (corcoran@corcoran-ota.com)



Kensington Pointe\_Site Plan\_... 402 KB

#### Good evening,

Please see the tabular data and our responses below. I have attached the previously sent site plan and to note, we anticipate having a full rendering available sometime next week.

HR-2 STANDARD	REQUIRED/ALLOWED	PROVIDED/PROPOSED	COMPLIANCE
MAX. D.U.s/ACRE (BASE, W/BONUSES)	Base: 40 d.u.s/ac W/Bonuses: 60 d.u.s/ac.	52 units/acre	Yes
MIN. OPEN SPACE	15 <u>UR1]</u> %	37%	Yes
MIN. LOT AREA	12,500 s.f.	187,308 s,f,	Yes
MIN. LOT WIDTH	100 ft.	845 feet (Memorial Dr)	Yes
MIN. TRANSITIONAL BUFFER	None Required (abuts HR-3 zoned properties)	20° minimum	Yes


FRONT SETBACK (For entire bldg. site)	Min 10 ft, Max 20 feet	10' from the curb	Yes
REAR SETBACK	20 ft.	20'	Yes
MINIMUM UNIT SIZE	650 s.f.	745 SF	<mark>Yes</mark>
MAX. BLDG. HEIGHT	8 stories or 100 ft	5 stories	Yes
TRANS'L HEIGHT PLANE	Applicable on north side abutting Kensington Road	Applicant indicates will comply.	Yes
OUTDOOR PLAY AREA	Min. area of 5% of total lot area or 4,000 s.f., whichever is greater 5% of lot area = 10,367 s.f.	23, 509 SF (12.8%)	Yes
PARKING	Min. –  Senior Housing5 spaces per dwelling unit. plus .25 spaces per du for guest parking (98 spaces)  Multi-Family—1.5 spaces per unit (180 spaces)  Office—1 space per 500 s.f. (32 spaces)	340 Total Spaces	Yes


PARKING	Min. – Senior Housing5 spaces per dwelling unit. plus .25 spaces per du for guest parking (98 spaces) Multi-Family—1.5 spaces per unit (180 spaces) Office—1 space per 500 s.f. (32 spaces) TOTAL REQUIRED = 310 parking spaces	340 Total Spaces	Yes
SIDEWALKS	10-ft. sidewalk. 10-ft.	10-ft cirlewalk 5-ft.	Yas: we will redesion for 10ft. landscape strin: however this is not included in the current site plan. Please see the comment 6 below.
AND	landscape strip, street trees	landscape strip, street	
STREETSCAPING	40 ft. on center.	trees 40 ft. on center.	


### **ZONING MAP**



### **Future Land Use Map**







## Kensington Station Development

DeKalb County Planning & Sustainability Department



### Purpose

Provide a supplemental report of land use policy analysis, existing studies, and Transit Oriented Development in the Kensington MARTA Station immediate area. Show the impact of proposed and existing development in the area.




### Kensington Station Existing Policy and Community Vision

• Kensington LCI plan (2003)

• Kensington LCI/TOD Supplemental Plan (2012)

• Regional Activity Center



### Kensington Station LCI Plan (2003)

### Policy Highlights

- The original planning effort focused on revitalizing potentially sustainable mixed-use activity centers.
- Through urban design and market analysis, the area surrounding the Kensington MARTA Station was selected as a mixed use activity center

#### SUB - AREAS

#### **Future Land Use Policy**

- Single-Family Preservation Maintain new and established single-family core along Old Rockbridge, Porter Road, and in Avondale Estates.
- DeKalb County Government Center Node
  - Consolidate and relocate existing uses scattered throughout the County.
  - Build new government administrative facilities.
  - Build new central open space quadrangle.

#### C. Regional Employment Center


- Potential long term development site for high-density office development or conference center.
- Redevelop of single-family residential to compatible office development.
- Create pedestrian and vehicular connections and access.
- Multi-Family Redevelopment Redevelop aging multi-family housing.
- Open Space Enhancements Connect existing undeveloped land along MARTA rail alignment to the County's greenway system with trails and pedestrian improvements.

### G. Mixed-Use

Redevelopment(Scattered Sites)
Redevelop aging neighborhood
oriented retail along Memorial
Drive and Covington Highway

- 1. Government Center Improvements
- 2. Employment Center Improvements
- 3. Kensington Station Plaza
- 4. Bus Rapid Transit Long-term Alternative 1
- 5. Bus Rapid Transit Short-term Alternative 2
- Greenway Connection Improvements

### Kensington Station Activity Center Small Area Plan (SAP)



### Kensington LCI Supplemental Study (2012)

### Policy Highlights

- to as a
  "supplemental" plan,
  which focuses mostly
  on areas directly
  around the MARTA
  station.
- The supplemental plan does not negate the policies of the 2003 LCI Plan.

# Kensington Livable Centers Initiative TRANSIT ORIENTED DEVELOPMENT PLAN



September 7, 2012

### Regional Center Future Land Use Map


### Policy Highlights

- To promote the concentration of regional serving activities to a centralized location that allow for a variety of uses.
- Regional Center is the highest land use designation in the county.

### DeKalb County Future Land Use Map

### Legend





Proposed Applicant: MARTA POC: Gregg Lloyd Address: 4200 Memorial Drive; 3393, 3391 and 3383 Kensington Road

Land Use: Regional Activity Center Proposed Use: 200 Multi-family Units Amendment needed? No Proposed Rezone: R-75 to MU4 or MU5 Consistent? YES

Map Prepared by: Long Range Planning DeKaib County Planning and Sustainability Department



The intent of the Regional Activity Center is to promote the concentration of regional serving activities to a centralized location that allow for a variety of uses while reducing automobile travel, promoting walkability and increased transit usage. These areas consist of a high intensity of regional commercial, office, employment areas and higher-education facilities. These areas are characterized by high vehicular traffic, and high transit use, including stops, shelters and transfer points. The areas also have onsite parking, high floor-area-ratios, large tracts of land, and campus or unified development. The proposed density for areas of this type allows up to 120 dwelling units per acre, with a preferable minimum of 10 stories, no maximum.


Primary Land Uses	Permitted Zaning
Tourisones     Continueum     Apartments     Health Care Pacition     Retail and Commercial     Office     Institutional Uses     Tourisonment and Cultural Facilities     Park and Recreators Pacities     Parks and Ciris Facilities	MU-5 MU-4 MU-3 MU-2 MR-1 MR-2 C-1 Or HR-1 HR-2 HR-3

#### Design Guidelines

- Setbacks Greater setbacks shall be required when adjacent to lower density residential uses and transitional buffers may be required.
- Buffers Development shall incorporate enhanced buffers in an effort to protect single family neighborhoods.
- Heights Proposed development shall consider and implement staggered heights when adjacent to single family residential neighborhoods.

### All Three Policy Recommendations

- COMMERCIAL low scale retail with storefronts and on-street parking.
- RESIDENTIAL Condos, walkup apartments and townhouses constructed out of brick and with traditional facades, private entrances and pedestrian orientation.
- TRANSPORTATION -included streetscapes with decorative pavers, cross walks, street trees, bike racks and lighting.
- OPEN SPACE -green space with seating areas and public gathering areas.
- MIXED-USE -Low density (3 to 5 stories) mixed-use buildings. Ground floor retail with office or residential above rated most appropriate for the Kensington area.





# Kensington Station

Surrounding Development Analysis

### Kensington Approved Rezoning Cases

### Residential

Townhome, Condos, Single Family Housing

### Mixed-Used

Retail, Commercial, office

Cases	Residential	Mixed-Used
2017	2	2
2018	1	0
2019	1	0

### DeKalb Major Projects (MARTA Areas)

### Avondale Forest

Status: Development in progress (t) appx 25% Description: Mixed-use, 373 MF units of residential. Within a TAD & the Kensington LCI Plan. Developer: Shelton McNally Real Estate Partners.

Estimated Cost: \$5M Comm. District: 4/6

#### 2. Avondale Estates

Status: Acquisition in pro-

Description: Approximately 4.3 acres. Estimated Cost: N/A Comm. District: 4/6

#### LDG Mixed Used Project Status:

Description: Up to 855 is multi-family development, with a few office spaces. Square footage is 426,588. Tax credits are involved. This project is

also within the Kensington

LCI Plan. Estimated Cost: \$4M Comm. District: 4/6

### 4. Oak Tree VIII as

Status: Developer Interest, no applications have been filed.

Loss tion: Memorial Drive Comm. District: 3/7

### Townhomes

Status:

Location: Porter Rd.

Description: Approximately 9 acres. Rezoned
from R-75 (Residential
Medium Lot) district to MU
-1 (Mixed use low density)
to develop 60 attached
townhome units, with an
amenity area and approximately 40,000 square feet
of retail development.
Comm. District: 3/7

#### 6. Sunri se

Status: Currently under construction.

Description: LD G is the developer. Mixed use project with 40,000 sf of non-residential and 200 plus units of residential. Estimated C ost: \$39M Comm. Districts: 5/7

#### 7. Paldela Property

Status: Developer Interest, No applications fied. Location: Red an Road Description: Approximately 13 acres. Town Center land use designation (mixed-use). Within Kensington-Memorial Overlay.

Comm. Districts: 5/6

8. Hamby Property

Status: Developer interest. No applications filed. Location: Red an Road Description: Proposed mixed-use. Town Center land use designation and within the Kensington Memorial Overlay District. District: 5/7

#### 9. Ambling Grove

Status: BOC Rezoning Hearing. Recommendation pending. Loss tion:

Description: Proposed new development of 120unit single family attached townhomes, with a density of 11du/ac.

Developer: Morris, Manning, & Martin

Comm. Districts: 5/7

### 10. **AHS**

Status: Rezoning

Hearing Units: 220


### Notes:


The projects mentioned above are not ALL of the development activity that is occurring within DeKalb County. They represent development that is occurring mostly around the Kensington and Indian Creek MARTA stations. These projects are in various stages from interest to land development, that have been in our pipeline from 2018-2010. Planning staff will continue to monitor and update development status.

### Planning and Development Current Activity 2019 Major Projects MARTA Areas

Prepared by: Long Range Planning, DeKallo County Planning, and Sustainability. https://www.dekalbcountyga.gov/planning-and-sustainability/planning-sustainability.









Avondale Estates
Status: Acquisition in process.

**Description:** 

Approximately 4.3 acres.

Estimated Cost: N/A Comm. District: 4/6



LDG Mixed Used Project Status:

Description: Up to 855 is multi-family development, with a few office spaces. Square footage is 426,588. Tax credits are involved. This project is also within the

Kensington LCI Plan. Estimated Cost: \$4M

Comm. District: 4/6



855 Units



AHS Project: Rezoned to a HR-3 (High Density Residential-3) to build ground level retail in combination with 220 apartment units within two - 7 seven-story buildings. contains 2.3 acres.

220 Units

MARTA Kensington Station Conceptual Land Use Framework for MU-4 Zoning

MARTA
Proposed Senior
Housing
Development

Units TBD

90 Units





## KENSINGTON STATION Future Development



# MARTA Kensington Station Rezoning





March 24, 2020

Mr. Andrew Baker, Director DeKalb County – Department of Planning & Sustainability Clark Harrison Building 330 W. Ponce de Leon Avenue Decatur, GA 30030

Subject: MARTA Kensington Station Rezoning Application

Dear Mr. Baker:

MARTA is requesting the rezoning of the Kensington MARTA Station from R-75 (Residential Medium Lot-75), C-1 (Commercial Local) and MR-2 (Medium Density Residential-2) to MU-4 (Mixed-Use High Density) to support mixed-use, transit-oriented development at the station. Current uses include the transit station/bus loop, traction power sub-station, surface parking, detention pond, and undeveloped land.

The MU-4 zoning classification is more in keeping with the community's vision for transitoriented development at the station as defined in both the 2003 and 2012 Atlanta Regional Commission's Livable Centers Initiative Plans as well as the 2035 Comprehensive Plan.

Currently, MARTA and the Housing Authority of DeKalb County (HADC) are negotiating the development of senior housing on MARTA's off-site property just south of Kensington Road (Parcels 1525103001, 152103002, and 152103003). This proposed development will serve as a first step toward development of the Regional Center as prescribed the County's 2035 Comprehensive Plan.

We are hopeful that the rezoning request is favorably received by DeKalb County. If you have any questions, please do not hesitate to contact me at 404-848-5011 or by email at dfrank@itsmarta.com.

Datti -

Debbie Frank

Director of Transit Oriented Development

Attachments:

 Melissa Mullinax, Chief of Staff Jacob Vallo, Sr. Director – TOD, Real Estate and Art in Transit

#### Households By Income

The largest group: <\$15,000 (15.9%) The smallest group: \$200,000+ (5.1%)

Indicator	Value	Difference	9
<\$15,000	15.9%	+7.1%	
\$15,000 - \$24,999	15.6%	+7.2%	
\$25,000 - \$34,999	12.1%	+3.4%	
\$35,000 - \$49,999	13.3%	+1.1%	
\$50,000 - \$74,999	15.1%	-3.8%	
\$75,000 - \$99,999	7.5%	-5.7%	
\$100,000 - \$149,999	9.4%	-5.1%	
\$150,000 - \$199,999	5.8%	-0.9%	
\$200,000+	5.1%	-3.5%	

Bars show deviation from **DeKalb County** 

#### Race and Ethnicity

The largest group: Black Alone (71.35)

The smallest group: Pacific Islander Alone (0.01)

Indicator	Value	Difference	е
White Alone	21.67	-9.98	
Black Alone	71.35	+17.32	
American Indian/Alaska Native Alone	0.11	-0.19	
Asian Alone	3.38	-3.68	
Pacific Islander Alone	0.01	-0.04	
Other Race	1.06	-3.08	
Two or More Races	2.42	-0.35	
Hispanic Origin (Any Race)	3.66	-5.38	

Bars show deviation from **DeKalb County** 

#### KENSINGTON MARTA STATION DEMOGRAPHICS

32.7 \$40,964 \$261,453 48 14,618 5,011 2.34 60

Population Households Avg Size Household

Median Median Age

Median Household Income Home Value Wealth Index

Diversity Index

#### HOUSING TENURE




2019 Owner Occupied Housing Units (Esri) (%)



2019 Vacant Housing Units (Esri) (%)



2019 Renter Occupied Housing Units (Esri) (%)



INCOME



\$40,964 Median Household Income



\$25,332

Per Capita Income



\$14,530

Median Net Worth





\$261,453

Median Home Value

<1939



\$5,970

Mortgage & Basics

1970-79

Average Spent on

1990-99



\$665

Median Contract Rent

2013-2017

**POVERTY** 



24%

2013-2017 ACS Households Below the Poverty Level (%)




1950-59




This infographic contains data provided by American Community Survey (ACS), Esri, Esri and Bureau of Labor Statistics. The vintage of the data is 2014-2018, 2019, 2024.

### Kensington Station Area Median Housing Values (Census Tract Level)



Produced by the DeKalb County Department of Planning and Sustainability (Long Range Planning Division) 4/2020 Source: American Community Survey 2014-2018 5 year estimates as prepared by the Atlanta Regional Commission



WHAT IS MARTA POLICY ON TOD?



## MARTA Guidelines & Policies TOD Guidelines

We've adopted a defined set of guidelines that provide a framework for designing and constructing successful TOD projects. These guidelines focus on creating developments that benefit MARTA and the surrounding communities and are built on four foundational principles: Station-area development that is compact and dense relative to its surroundings.

- 1. TOD seeks higher density for a simple reason: concentrated developments makes it possible for people to live, work, shop and go to school within walking distance of MARTA. This not only generates revenue for MARTA and other transit providers, but it also allows residents to make regular use of alternative transit.
- 2..A rich mix of land uses. TOD creates mixed-use developments that help people live all their lives more conveniently. By taking a live-work-play approach to these station areas, TOD strengthens the link between transit and development. 3.The areas become more than transit hubs or stops on a route.

They become destinations where people choose to spend their days — all with the convenience of onsite transit.

4.A great public realm. TOD places people and pedestrians first, especially within the quarter-mile radius involved in most daily commutes. In a mixed-use environment, short blocks and grid-based sidewalks navigate throughout the development. These streets, sidewalks, plazas and transit stations are safe and accessible — dotted with attractive amenities, clear lighting and easy-to-follow wayfinding.

A new approach to parking. Even with high transit utilization, people still use cars to come and go — and they'll need a place to park when they do. TOD aims to make parking a natural, non-dominant aspect of mixed-use developments, reducing the number of necessary spaces and providing incentives that regularly free up parking. All the while, these parking spaces are designed to blend in directly with the overall look and feel of the area.



We create JOY in our communities by connecting people to jobs, food, healthcare, education, housing, greenspace, sport and love — all accessible through public transit.

## MARTA's Brookhaven / Oglethorpe Station





Concept plan for the Brookhaven-Oglethorpe MARTA redevelopment include a central plaza area, tennis courts, a swimming pool area within residential units, townhomes and ground floor retail. (City of Brookhaven)




## Lindbergh Train Station

MARTA Lindbergh Center Station Tour













#### DEKALB COUNTY GOVERNMENT PLANNING DEPARTMENT DISTRIBUTION FORM

NOTE: PLEASE RETURN ALL COMMENTS VIA EMAIL OR FAX TO EXPEDITE THE PROCESS TO MICHELLE ALEXANDER mmalexander@dekalbcountyga.gov AND/OR LASONDRA HILL lahill@dekalbcountyga.gov

### COMMENTS FORM: PUBLIC WORKS TRAFFIC ENGINEERING

10 1120-1

Case No.: 2-20-12936 +6 Parcel I.D. #: 13	7 03 0-, 00-00 /	
Address: Kenscingszume Rd	•	
Menoral		
Dec a co		
DECAME OF		
Adjacent Ro	adway (s):	
(classification)	(classification)	
Capacity (TPD)	Capacity (TPD)	
Latest Count (TPD)	Latest Count (TPD)	
Hourly Capacity (VPH)	Hourly Capacity (VPH)	
Peak Hour. Volume (VPH)	Peak Hour. Volume (VPH)	
Existing number of traffic lanes Existing right of way width	Existing number of traffic lanes Existing right of way width	-
Proposed number of traffic lanes	Proposed number of traffic lanes	-
Proposed right of way width	Proposed right of way width	-
Please provide additional information relating to the following stat	ement.	
According to studies conducted by the Institute of Traffic Engineer generate an average of fifteen (15) vehicle trip end (VTE) per 1, 000 factor. Based on the above formula, thesquare foot place owith approximatelypeak hour vehicle trip ends.	O square feet of floor area, with an eight (8%) p	ercent peak hour
Single Family residence, on the other hand, would generate ten (10 peak hour factor. Based on the above referenced formula, the a maximum of units per acres, and the given fact that the proj vehicle trip end, and peak hour vehicle trip end would be gener	(Single Family Residential) District designat ect site is approximately acres in land are	ion which allows a,daily
COMMENTS:		
RELIENDE And found NO dis Rupor Tapoffic Plan.	problem that wo	uld
	40.40.4	
	As David	MLOSI

Signature:



## DEKALB COUNTY GOVERNMENT PLANNING DEPARTMENT DISTRIBUTION FORM

The following areas below may warrant comments from the Development Division. Please respond accordingly as the issues relate to the proposed request and the site plan enclosed as it relates to Chapter 14. You may address applicable disciplines.

#### **DEVELOPMENT ANALYSIS:**

#### Transportation/Access/Row

Consult the Georgia DOT as well as the DeKalb County Transportation Department prior to land development permit. Verify widths from the centerline of the roadways to the property line for possible right-of-way dedication. Improvements within the right-of-way may be required as a condition for land development application review approval. Safe vehicular circulation is required. Paved off-street parking is required.

#### • Storm Water Management

Compliance with the Georgia Stormwater Management Manual, DeKalb County Code of Ordinances 14-40 for Stormwater Management and 14-42 for Storm Water Quality Control, to include Runoff Reduction Volume where applicable is required as a condition of land development permit approval. Use Volume Three of the G.S.M.M. for best maintenance practices. Use the NOAA Atlas 14 Point Precipitation Data set specific to the site.. Recommend Low Impact Development features/ Green Infrastructure be included in the proposed site design to protect as much as practicable the statewaters and special flood hazard areas.

#### • Flood Hazard Area/Wetlands

The presence of FEMA Flood Hazard Area was not indicated in the County G.I.S. mapping records for the site; and should be noted in the plans at the time of any land development permit application. Encroachment of flood hazard areas require compliance with Article IV of Chapter 14 and FEMA floodplain regulations.

#### • Landscaping/Tree Preservation

Landscaping and tree preservation plans for any building, or parking lot must comply with DeKalb County Code of Ordinances 14-39 as well as Chapter 27 Article 5 and are subject to approval from the County Arborist.

#### • Tributary Buffer

State water buffer was not reflected in the G.I.S. records for the site. Typical state waters buffer have a 75' undisturbed stream buffer and land development within the undisturbed creek buffer is prohibited without a variance per DeKalb County Code of Ordinances 14-44.1.

#### Fire Safety

<u>Plans for land development permit must comply with Chapter 12 DeKalb County Code for fire protection and prevention.</u>

From: Keeter, Patrece
To: Hill, LaSondra

 Subject:
 Zoning Comments April 2020

 Date:
 Monday, April 13, 2020 5:48:42 PM

Attachments: image006.png

image008.png image010.png image003.emz image005.png image007.jpg image011.png image011.png image017.png

N1 & N2- Panthersville Road is classified as a minor arterial. 6 foot sidewalks, Bike lanes, Street lights (SL Engineer: <a href="mailto:hefowler@dekalbcountyga.gov">hefowler@dekalbcountyga.gov</a>) and 40 foot right of way dedication from centerline required (see Land Development Code 14-190 and Zoning Code page 5-14). Ensure driveway has intersection and stopping sight distance based on AASHTO standards- provide sign and sealed engineer's study of sight distance.

N3. Memorial Drive is a state route. GDOT review and approval required prior to permitting. Memorial Drive is classified as a major arterial. 6 foot sidewalks, Bike lanes, Street lights (SL Engineer: <a href="hefowler@dekalbcountyga.gov">hefowler@dekalbcountyga.gov</a>) and 50 of right of way dedication from centerline or the amount needed for all public infrastructure (Sidewalks, bike lanes, lanes, street lights) required, whichever greater (see Land Development Code 14-190 and Zoning Code page 5-14). Midway Road is classified as a collector. 6 foot sidewalks, Bike lanes, Street lights (SL Engineer: <a href="hefowler@dekalbcountyga.gov">hefowler@dekalbcountyga.gov</a>) and 35 feet of right of way dedication from centerline or the amount needed for all public infrastructure (Sidewalks, bike lanes, street lights) required, whichever greater (see Land Development Code 14-190 and Zoning Code page 5-14). Ensure driveway has intersection and stopping sight distance based on AASHTO standards- provide sign and sealed engineer's study of sight distance.

N4. See chapter 5 of the zoning code- traffic study required. 448 units requires more access points. See section 14-200 of the land development code. Memorial Drive is a state route. GDOT review and approval. required prior to permitting. Memorial is classified as a major arterial. 6 foot sidewalks, Bike lanes, Street lights (SL Engineer: <a href="hefowler@dekalbcountyga.gov">hefowler@dekalbcountyga.gov</a>) and 50 feet of right of way dedication from centerline or the amount needed for all public infrastructure (Sidewalks, bike lanes, lanes, street lights) required, whichever greater (see Land Development Code 14-190 and Zoning Code page 5-14). If you variances for bike lanes, I suggest you request this as part of zoning. Ensure driveway has intersection and stopping sight distance based on AASHTO standards- provide sign and sealed engineer's study of sight distance.

N5. Lawrenceville Hwy is a state route classified as a major arterial. GDOT review and approval. required prior to permitting. 6 foot sidewalks, Bike lanes, Street lights (SL Engineer: hefowler@dekalbcountyga.gov) and 50 feet of right of way dedication from centerline or the amount needed for all public infrastructure (Sidewalks, bike lanes, lanes, street lights) required, whichever greater (see Land Development Code 14-190 and Zoning Code page 5-14). If you variances for bike lanes, I suggest you request this as part of zoning. Haralson Rd is classified as a local road. 5 foot sidewalks, Street lights (SL Engineer: hefowler@dekalbcountyga.gov) and 27.5 feet right of way dedication from centerline or the amount needed for all public infrastructure (Sidewalks, bike lanes, lanes, street lights) required, whichever greater (see Land Development Code 14-190 and Zoning Code page 5-14). Ensure driveway has intersection and stopping sight distance

based on AASHTO standards- provide sign and sealed engineer's study of sight distance. N6. East Conley Rd is classified as a collector. 6 foot sidewalks, Bike lanes, Street lights (SL Engineer: <a href="hefowler@dekalbcountyga.gov">hefowler@dekalbcountyga.gov</a>) and 50 feet of right of way dedication from centerline or the amount needed for all public infrastructure (Sidewalks, bike lanes, lanes, street lights) required, whichever greater (see Land Development Code 14-190 and Zoning Code page 5-14). If you variances for bike lanes, I suggest you request this as part of zoning. Ensure driveway has intersection and stopping sight distance based on AASHTO standards- provide sign and sealed engineer's study of sight distance.

N7. East Conley Rd is classified as a collector. 6 foot sidewalks, Bike lanes, Street lights (SL Engineer: <a href="hefowler@dekalbcountyga.gov">hefowler@dekalbcountyga.gov</a>) and 50 feet of right of way dedication from centerline or the amount needed for all public infrastructure (Sidewalks, bike lanes, lanes, street lights) required, whichever greater (see Land Development Code 14-190 and Zoning Code page 5-14). If you variances for bike lanes, I suggest you request this as part of zoning. Ensure driveway has intersection and stopping sight distance based on AASHTO standards- provide sign and sealed engineer's study of sight distance.

N8. North Druid Hills Road is classified as a major arterial. 6 foot sidewalks, Bike lanes, Street lights (SL Engineer: <a href="hefowler@dekalbcountyga.gov">hefowler@dekalbcountyga.gov</a>) and 50 feet of right of way dedication from centerline or the amount needed for all public infrastructure (Sidewalks, bike lanes, lanes, street lights) required, whichever greater (see Land Development Code 14-190 and Zoning Code page 5-14). Ensure driveway has intersection and stopping sight distance based on AASHTO standards- provide sign and sealed engineer's study of sight distance. Ensure that the driveway either lines up with the Knob Hill or is at the appropriate offset in section 14-200 of the land development code. Interior road to be privately maintained.

N9. Stephenson Road is classified as a collector road. 6 foot sidewalks, Bike lanes, Street lights (SL Engineer: <a href="hefowler@dekalbcountyga.gov">hefowler@dekalbcountyga.gov</a>) and 35 feet of right of way dedication from centerline or the amount needed for all public infrastructure (Sidewalks, bike lanes, lanes, street lights) required, whichever greater (see Land Development Code 14-190 and Zoning Code page 5-14). Ensure driveway has intersection and stopping sight distance based on AASHTO standards- provide sign and sealed engineer's study of sight distance. For more that 150 units, the code requires two access points. I would like more details on the proposed super entrance, but would generally support a variance for the extra 10 lots with the addition of sidewalk along the entire frontage and along the frontage of the Calvary Church within the existing ROW.

N10. Sherrydale Ln is classified as a local road. 5 foot sidewalks, Street lights (SL Engineer: <a href="hefowler@dekalbcountyga.gov">hefowler@dekalbcountyga.gov</a>) and 27.5 feet right of way dedication from centerline or the amount needed for all public infrastructure (Sidewalks, bike lanes, lanes, street lights) required, whichever greater (see Land Development Code 14-190 and Zoning Code page 5-14). Interior streets to remain private.

N11. No comment

N12. No comment

N13. This appears to be a DRI. As I recall, the county can not take any zoning actions until the traffic study is submitted and reviewed by the regional partners, including ARC, GDOT and GRTA. Taking action on this item can put our federal transportation funding at risk. If this is not considered to be a DRI, I would still need a traffic study completed to make appropriate zoning comments to identify necessary improvements. Transportation has currently applied for federal funding to complete road diets on Mountain Drive (state route) and Kensington Road. In addition, we have applied for federal

funding to wrap this development area in a multiuse path to promote development and multi-modal connectivity. Memorial Drive and Covington Hwy are state routes classified as major arterials. GDOT review and approval. required prior to permitting. 6 foot sidewalks, Bike lanes, Street lights (SL Engineer: hefowler@dekalbcountyga.gov) and 50 feet of right of way dedication from centerline or the amount needed for all public infrastructure (Sidewalks, bike lanes, lanes, street lights) required, whichever greater (see Land Development Code 14-190 and Zoning Code page 5-14). Mountain Drive is a state route classified as a collector. GDOT review and approval required prior to permitting. 6 foot sidewalks, Bike lanes, Street lights (SL Engineer: hefowler@dekalbcountyga.gov) and 35 feet of right of way dedication from centerline or the amount needed for all public infrastructure (Sidewalks, bike lanes, street lights) required, whichever greater (see Land Development Code 14-190 and Zoning Code page 5-14). Kensington Road is classified as a minor arterial. 6 foot sidewalks, Bike lanes, Street lights (SL Engineer: <a href="mailto:hefowler@dekalbcountyga.gov">hefowler@dekalbcountyga.gov</a>) and 40 feet of right of way dedication from centerline or the amount needed for all public infrastructure (Sidewalks, bike lanes, lanes, street lights) required, whichever greater (see Land Development Code 14-190 and Zoning Code page 5-14). Ensure driveway has intersection and stopping sight distance based on AASHTO standards- provide sign and sealed engineer's study of sight distance. Watch driveway offsets required in Section 14-200 of the land development code (existing and already permitted driveways). This will be more units than the code allows. Intersection improvements and upgrades to protect capacity (median islands) will most likely be required. At a minimum: analyze roundabouts as design solutions for driveway access on Mountain and Kensington, provide enhanced pedestrian crossings on Kensington and Mountain, provide direct pedestrian accommodations from the sidewalks on public right of way to the entrances of the development. N14 & N15- This should all be packaged with the DRI in N13. See comments on N13.

#### Patrece G. Keeter, P.E.

Engineering Manager, Department of Public Works Transportation Division

1950 West Exchange Place, 4<sup>th</sup> FL Tucker, Georgia 30084 pgkeeter@dekalbcountyga.gov 770-492-5281 678-758-3860 DeKalbCountyGA.gov





#### 04/08/2020

To: Mr. John Reid, Senior Planner

From: Ryan Cira, Environmental Health Manager Cc: Alan Gaines, Technical Services Manager

Re: Rezone Application Review

#### **General Comments:**

DeKalb County Health Regulations prohibit use of on-site sewage disposal systems for

- multiple dwellings
- · food service establishments
- hotels and motels
- · commercial laundries
- funeral homes
- schools
- nursing care facilities
- personal care homes with more than six (6) clients
- child or adult day care facilities with more than six (6) clients
- residential facilities containing food service establishments

If proposal will use on-site sewage disposal, please contact the Land Use Section (404) 508-7900.

Any proposal, which will alter wastewater flow to an on-site sewage disposal system, must be reviewed by this office prior to construction.

This office must approve any proposed food service operation or swimming pool prior to starting construction.

Public health recommends the inclusion of sidewalks to continue a preexisting sidewalk network or begin a new sidewalk network. Sidewalks can provide safe and convenient pedestrian access to a community-oriented facility and access to adjacent facilities and neighborhoods.

For a public transportation route, there shall be a 5ft. sidewalk with a buffer between the sidewalk and the road. There shall be enough space next to sidewalk for bus shelter's concrete pad installation. Recommendation: Provide trash can with liner at each bus stop with bench and monitor for proper removal of waste.

Since DeKalb County is classified as a Zone 1 radon county, this office recommends the use of radon resistant construction.

#### Board of Health

NI 1	7 20 12	12200 202	0 00 10 /	15-023-01-008
N.1	Z-ZU-1Z4	13/89 ZUZI	U-U.3 IU /	コラーロススーロコーロロと

4201 PANTHERSVILLE RD, ELLENWOOD, GA 30294

- Septic system installed on 09/07/1962

#### N.2 **SLUP-20-1243788 2020-0311 / 15-023-01-008**

4201 PANTHERSVILLE RD, ELLENWOOD, GA 30294

- Septic System installed on 06/07/1962

#### N.3 **N3 SLUP-20-1243831 2020-0312 /15-217-12-003**

3585 MEMORIAL DR, DECATUR, GA 30032

- Please review general comments

#### N.4 **Z-20-1243836 2020-0313 / 15-230-01-010**

4213, 4203, 4195, 4187, 4179, 4183, & 4159 MEMORIAL DR, DECATUR, GA 30032

- Please review general comments

#### N.5 **Z-20-1243837 2020-0314 / 18-146-02-081**

2550 LAWRENCEVILLE HWY, DECATUR, GA 30033

- Septic system installed on 10/18/1989

#### N.6 **Z-20-1243838 2020-0315 / 15-013-01-017; 15-013-01-018**

4321 & 4341 E CONLEY RD, CONLEY, GA 30288

- Please review general comments

#### N.7 **Z-20-1243839 2020-0316 / 15-013-02-017**

4388 E CONLEY RD, CONLEY, GA 30288

- Please review general comments

#### N.8 **Z-20-1243840 2020-0317 / 18-152-03-006**

2573 N DRUID HILLS RD, ATLANTA, GA 30329

- Septic system installed on 05/02/1963

#### N.9 **Z-20-1243841 2020-0318/ 16-159-01-003; 16-162-05-002**

1467 & 1503 STEPHENSON RD, LITHONIA, GA 30058

- Please review general comments

#### N.10 **Z-20-1243847 2020-0319 / 15-197-01-001**

3559 SHERRYDALE LN, DECATUR, GA 30032

- Please review general comments

#### N.11 **CZ-20-1243853 2020-0320/ 15-251-01-028**

3458, 3468 & 3478 MOUNTAIN DR, DECATUR, GA 30032

**DeKalb County Board of Health** 

445 Winn Way – Box 987

Decatur, GA 30031

404.294.3700 • www.dekalbhealth.net

#### Board of Health

- Please review general comments
- N.12 **SLUP-20-1243861 2020-0331 / 15-041-01-152**

2902 CEDAR TRACE ROAD, ELLENWOOD, GA 30294

- Please review general comments
- N.13 Z-20-1243878 2020-0387 / 15-250-07-001, 15-250-07-003, 15-250-07-005, 15-250-07-006, 15-250-07-007, 15-250-07-008, 15-250-07-009, 15-250-07-010, 15-250-07-011, 15-250-07-012, 15-250-07-013, 15-250-07-014, 15-250-07-016, 15-250-07-017, 15-250-07-018, 15-250-07-019, 15-250-07-020, 15-250-07-021, 15-250-07-022, 15-250-07-023, 15-250-07-024, 15-250-07-025, 15-250-07-026, 15-251-02-001, 15-251-02-002, 15-251-02-003, 15-251-02-004, 15-251-02-005, 15-251-02-006, 15-251-02-007, 15-251-02-016
  - 3350 KENSINGTON RD, (AND OTHERS), DECATUR, GA 30032
  - Please review general comments
- N.14 **Z-20-1243876 2020-0385 / 15-250-06-009, 15-251-03-001,15-251-03-002, 15-251-03-003** 4200 MEMORIAL DR, DECATUR, GA 30032
  - Please review general comments
- N.15 **SLUP-20-1243877 2020-0386 / 15-250-06-009, 15-251-03-001,15-251-03-002, 15-251-03-003**4200 MEMORIAL DR, DECATUR, GA 30032
  - Please review general comments
- N.16 TA-20-1243897 2020-0414
  - Please review general comments



750 Commerce Drive • Suite 110 Decatur, GA 30030 p / f 470.440.8610

www.housingdevelopmentcorp.org

June 10, 2020

Mr. Andrew Baker, Director DeKalb County - Department of Planning & Sustainability Clark Harrison Building 330 W. Ponce de Leon Avenue Decatur, GA 30030

Subject: 3391 Kensington Rd. Rezoning Application

Dear Mr. Baker:

The Housing Development Corporation (an affiliate of the Housing Authority of DeKalb County) and MARTA are requesting the rezoning of parcels 1525103001, 1525103002, 1525103003 and 1525006009 from R-75 (Residential Medium Lot-75) to HR-2 (High Density Residential) to support mixed-use, transit-oriented development at the station. Current uses include the transit station/bus loop, traction power sub-station, surface parking, detention pond, and undeveloped land.

MARTA and the Housing Authority of DeKalb County (HADC) are negotiating the development of senior housing on MARTA's off-site property just south of Kensington Road. This proposed development will serve as a first step toward development of the Regional Center as prescribed the County's 2035 Comprehensive Plan.

The HR-2 zoning classification is more in keeping with the community's vision for transit- oriented development at the station as defined in both the 2003 and 2012 Atlanta Regional Commission's Livable Centers Initiative Plans as well as the 2035 Comprehensive Plan.

We are hopeful that the rezoning request is favorably received by DeKalb County. If you have any questions, please do not hesitate to contact me at 470-440-8594 or john.corcoran@theHDC.org.

Sincerely,

John Corcoran

Vice President & COO

Cc: Keri Taylor-Spann, VP of Development



404.371.2155 (e) 404.371.4556 (f) De Kalli Gauni yiqa gere Clark Harrison Building 330 W. Ponce de Leon Ave Decatur, GA 30030

Chief Executive Officer Michael Thurmond

#### DEPARTMENT OF PLANNING & SUSTAINABILITY

Director Andrew A. Baker, AICP

#### REZONING APPLICATION CHECKLIST

TIEDOTTION TO THE CONTROL OF THE CON
Submit 4 printed, collated sets of the complete application (no staples, no binders) and a PDF version on a flash drive
1. Schedule a mandatory Pre-Application Conference with Planning & Sustainability staff by appointment. Obtain Pre-
Application form (to be completed in pre-application meeting). Please call 404-371-2155 for appointment.
2. Hold a <u>Pre-Submittal Community Meeting</u> with surrounding neighborhood associations and residents. Provide documentation of the meeting (meeting notice and sign in sheets). Letter(s) from homeowners association(s) may also be provided.
3. Submit Application (Submit 4 printed, collated sets and a PDF version on a flash drive. Please assemble materials in
the following order.)
A. Application form with name and address of applicant and owner, and address of subject property;
B. Pre-submittal community meeting notice and sign-in sheet and other documentation of meeting, if any;
C. Letter of application and impact analysis
<ol> <li>Letter of application identifying a) the proposed zoning classification, b) the reason for the rezoning or special use or modification request, c) the existing and proposed use of the property, d) detailed characteristics of the proposed use (e.g. floor area, height of building(s), number of units, mix of unit types, number of employees, manner and hours of operation), d)(optional) statement of conditions discussed with the neighborhood or community, if any.</li> </ol>
<ol> <li>Impact analysis of the anticipated impact of the proposed use and rezoning on the surrounding properties in response to the standards and factors specified in Article 7.3 of the DeKalb County Zoning Ordinance, as attached. If a Major Modification, please include previously approved conditions and Board of Commissioner meeting minutes.</li> </ol>
D. Authorization Form, if applicant is not the owner. Must be signed by all owners of the subject property and notarized. Authorization must contain the mailing address and phone number of any applicant or agent who is authorized to represent the owner(s) of the subject property. Please include warranty deed, if property ownership is less than 2 years.  E. Campaign disclosure statement (required by State law).
F. Legal boundary survey of the subject property, (showing boundaries, structures, and improvements), prepared and sealed within the last year by a professional engineer or land surveyor registered in the State of Georgia. (If survey shows property on opposite sides of a public street right-of-way, file a separate application for each property.)
G. Site Plan, printed to scale, folded, of any existing and or proposed development/redevelopment. For projects
larger than 1 acre, site plan should be at least 1:50 scale. The site plan must include the following: a. complete boundaries of subject property;
b. dimensioned access points and vehicular circulation drives;
c. location of all existing and proposed buildings, structures, setbacks and parking;
d. location of 100 year floodplain and any streams;
e. notation of the total acreage or square footage of the subject property;
f. landscaping, tree removal and replacement, buffer(s); and
g. site plan notes of building square footages, heights, density calculations, lot coverage of impervious surfaces,
parking ratios, open space calculations, and other applicable district standards.
H. Reduced Site Plan, reduced to 8.5" x 11".
Written Legal Description of metes and bounds of the subject property (can be printed on site plan or survey).
J. Building Form Information. Elevation (line drawing or rendering), or details of proposed materials, in compliance
with Article 5 of the Zoning Ordinance

K. Completed, signed Pre-application Form (Provided at pre-application meeting.)



404.371.2155 (o) 404.371.4556 (f) De KalbCountyGa.gov

Clark Harrison Building 330 W. Ponce de Leon Ave Decatur, GA 30030

#### DEPARTMENT OF PLANNING & SUSTAINABILITY

## Rezoning Application to Amend the Official Zoning Map of DeKalb County, Georgia

		387
Applicant	Name:John Corcoran	
Applicant	E-Mail Address:john.corcoran@theHDC.org	
Applicant N	Mailing Address:750 Commerce Dr, Decatur, GA 30030	
Applicant D	Daytime Phone:470-440-8594 Fax:470-440-8594	
Owner Nar	me:Metropolitan Atlanta Rapid Transit Authority (MARTA)	
	If more than one owner, attach list of owners.	
Owner Mai	ling Address:2424 Piedmont Rd, Atlanta, GA 30324	
Owner Day	/time Phone:404-848-5011	
Address of	f Subject Property:3391 Kensington Rd, Decatur, GA 30032	
Parcel  5 25	10#:1525006009, 1525103001, 1525103002, 1525103003	
Parcel 15 25 Acreage	10#:1525006009, 1525103001, 1525103002, 1525103003	District



404.371.2155 (o) 404.371.4556 (f) DeKaibCountyGa.gov

Clark Harrison Building 330 W. Ponce de Leon Ave Decatur, GA 30030

#### DEPARTMENT OF PLANNING & SUSTAINABILITY

#### IMPACT ANALYSIS

(Please respond to the following standards and factors on a separate sheet.)

Section 27-7.3.5. The following standards and factors are found to be relevant to the exercise of the county's zoning powers and shall govern the review of all proposed amendments to the Official Zoning Map:

- A. Whether the zoning proposal is in conformity with the policy and intent of the Comprehensive Plan.
- B. Whether the zoning proposal will permit a use that is suitable in view of the use and development of adjacent and nearby properties.
- C. Whether the property to be affected by the zoning proposal has a reasonable economic use as currently zoned.
- D. Whether the zoning proposal will adversely affect the existing use of usability of adjacent or nearby properties.
- E. Whether there are other existing or changing conditions affecting the use and development of the property which give supporting grounds for either approval or disapproval of the zoning proposal.
- F. Whether the zoning proposal will adversely affect historic building, sites, districts, or archaeological resources.
- G. Whether the zoning proposal will result in a use which will or could cause excessive or burdensome use of existing streets, transportation facilities, utilities, or schools.
- H. Whether the zoning proposal adversely impacts the environment or surrounding natural resources.

#### Impact Analysis Responses

Section 27-7.3 5. The following standards and factors are found to be relevant to the exercise of the county's zoning powers and shall govern the review of all proposed amendments to the Official Zoning Map:

A. Whether the zoning proposal is in conformity with the policy and intent of the Comprehensive Plan. Yes. The 2035 Comprehensive Plan designates the MARTA Station within a Regional Center classification. In addition, the station has been the subject of a DeKalb County Small Area Plan and a 2012 Livable Centers Initiative Plan. These plans recommend high density mixed-use development. HR-2 is specifically listed as a permitted zoning district in the Regional Center classification.

- B. Whether the zoning proposal will permit a use that is suitable in view of the use and development of adjacent and nearby properties. Yes. In the past five years, properties along Kensington Road have transitioned to denser residential uses including HR-1 for a proposed development adjacent to this site. This proposal conforms with the changing land use pattern of the adjacent and nearby properties.
- C. Whether the property to be affected by the zoning proposal has a reasonable economic use as currently zoned. No. The property is currently zoned R-75 Residential Medium Lot. R-75 does not permit the density nor design features that would permit for the economic viability of the site to realize the type of development envisioned by the Comprehensive Plan, which is high density mixed-use development.
- D. Whether the zoning proposal will adversely affect the existing use of usability of adjacent or nearby properties. No. The zoning proposal will complement the recent development pattern in the area.
- E. Whether there are other existing or changing conditions affecting the use and development of the property which give supporting grounds for either approval or disapproval of the zoning proposal. No. Other than the transitioning nature of the surrounding area from low density single-family to high density residential, there are no other supporting grounds for either approval or disapproval.
- F. Whether the zoning proposal will adversely affect historic building, sites, districts, or archaeological resources. No. There are no known historic buildings, sites, districts, or archaeological resources that will be adversely affected.
- G. Whether the zoning proposal will result in a use which will or could cause excessive or burdensome use of existing streets, transportation facilities, utilities, or schools. TBD. MARTA along with our development partner will evaluate the potential ancillary impacts of this development and incorporate any mitigation plans into the final design and construction.
- H. Whether the zoning proposal adversely impacts the environment or surrounding natural resources. No. There are no known impacts to the environment or surrounding natural resources that will be adversely impacted.



Clark Harrison Building 330 W. Ponce de Leon Ave Decatur, GA 30030

#### DEPARTMENT OF PLANNING & SUSTAINABILITY

#### DISCLOSURE OF CAMPAIGN CONTRIBUTION

In accordance with the Conflict of Interest in Zoning Act, OCGA Chapter 36-67A, the following questions must be answered.

Have you, the applicant, made \$250.00 or more in campaign contribution to a local government official within two years immediately preceding the filling of this application?

Vac	M-	X	*
Yes	No	_ ^	- 507

If the answer is yes, you must file a disclosure report with the governing authority of DeKalb County showing:

- The name and official position of the local government official to whom the campaign contribution was made.
- The dollar amount and description of each campaign contribution made during the two years immediately preceding the filing of this application and the date of each such contribution.

The disclosure must be filed within 10 days after the application is first filed and must be submitted to the C.E.O. <u>and</u> to the Board of Commissioners of DeKalb County, 1300 Commerce Drive, Decatur, GA 30030.

Notary

Signature of Applicant /Date

Check one: Owner\_\_\_\_\_ Agent \_\_X\_

\*Notary seal not needed if answer is "no".



404.371.2155 (o) 404.371.4556 (f) DeKalhCountyGa.gov Clark Harrison Building 330 W. Ponce de Leon Ave Decatur, GA 30030

#### DEPARTMENT OF PLANNING & SUSTAINABILITY

#### **AUTHORIZATION**

The property owner should complete this form or a similar signed and notarized form if the individual who will file the application with the County is not the property owner.

June 11, 2020 Date:	
TO WHOM IT MAY CONCERN:	
(I) (WE) Metropolitan Atlanta Rapid Tra	nsit Authority (MARTA)
	Name of owner(s)
being (owner) (owners) of the subject pro- delegate authority to	operty described below or attached hereby
Housing Development Corporation (an	affiliate of the Housing Authority of DeKalb County)
Sharon Rose Dunn E	PUBLIC SO SE Datta Frank Owner COUNTY INTERIOR
Notary Public	Owner
Notary Public	Owner
Notary Public	Owner







#### DEPARTMENT OF PLANNING & SUSTAINABILITY

#### **FILING FEES**


At the time of submittal, a filing fee shall accompany each application as follows:

Rezoning	FEE
RE, RLG, R-100, R-85, R-75, R-60	\$500.00
MHP, RNC, RSM, MR-1, MR-2	

\$750.00 HR-1, HR-2, HR-3 MU-1, MU-2, MU-3, MU-4, MU-5 O-I, OD, OIT, NS, C-1, C-2, M. M-2

If the application is a request to rezone to more than one zoning district, the higher fee will apply.

Applications for non-contiguous property (separated by a street) must be filed separately. A separate fee will be charged for each application. Applications deferred "full cycle" do not require additional fees. An application that is withdrawn and later re-filed will be treated as a new case and will require a new fee.





Keri Taylor-Spann < Keri.Taylor-Spann@thehdc.org >

Mon 6/15/2020 5:03 PM

To: Reid, John

Cc: Prince, Jahnee R.; John Corcoran < John.Corcoran@thehdc.org>; Frank, Debbie < dfrank@itsmarta.com>; Floyd, Greg < gfloyd@itsmarta.com>



Kensington Pointe DeKalb C... 2 MB



Kensington Pointe DeKalb C...

2 attachments (3 MB) Download all Save all to OneDrive - DeKalb County, Georgia

Good afternoon John Reid,

The applicant would like to request that the applications for Z-20-1243876 and SLUP-20-1243877 be amended to HR2 rather than MU4. The revised applications are attached.

Please note that this is the first draft of our revised HR-2 site plan and the architect is making requested revisions.

Thank You, Keri Taylor-Spann Vice President, Development



Housing Development Corporation

750 Commerce Drive, Suite 110 Development Decatur, GA 30030

keri.taylor@thehdc.org www.housingdevelopmentcorp.org