



QUOTATION

DATE - 6/15/2021 – REVISION #2
 QUOTE - # CB21-012

FROM - Chris Brown – P- 678-906-0827
 E-MAIL – cbrown@sseteam.com

PROJECT:	LOCATION:
Exchange Park	Decatur, GA

QUOTE CONTACT INFORMATION:

Contact Name	Nick Jovene	Contact Phone Number	970-227-2814
Contact Company	CGL	Contact E-Mail	njovene@cglcompanies.com

QUOTATION SPECIFICS:

Specification Section	NONE	Freight	Included
Product	Focus Gym Flooring	Installation	Included
Manufacture	Connor Sports	Tax @ 8%	Included
Approval Status	NONE	ADDENDUMS NOTED	NONE

BID PRICE:

\$176,295.00

**PRICING BELOW INCLUDES REMOVAL AND DISPOSAL OF EXISTING WOOD FLOOR AND
 INSTALL OF NEW FLOOR**

Quoting approximately (9,100 sq. ft) of “Focus” Gymnasium wood floor by Connor Sports. Floor system features a pre-assembled subfloor system with solid blocking, anchor pins, anchor clips and “continuous focus pads”. System height 1-3/4” using 25/32” X 2-1/4” wide 2nd or better grade Maple, A 4-color center logo and game lines for basketball, volleyball and pickleball are included. Vented cover base and new thresholds at all doors are also included.

Sourcewell contract # 060518-CSC

LINE ITEM # 145 Floor removal and demo \$5.00/ s.f. X 9,068=.....	\$ 45,340.00
Line item # 102 Focus with 25/32”x 2-1/4” Second & B \$17.69 X 9,068=.....	\$160,412.92
Line item # 42 Single color logo \$2,000 =	\$ 2,000.00
Line item # 43 additional color \$515 X 3=	\$ 1,545.00
TOTAL.....	\$209,297.92
SSE DISCOUNT	(\$33,002.92)

Grand Total\$176,295.00

DUE TO VOLATILITY IN THE WOOD MARKET CONNOR WILL NOT HONOR OR GUARANTEE ANY PRICING. UPON APPROVAL BY DEKALB COUNTY TO MOVE FORWARD A PRICE REQUEST MUST BE MADE TO VERIFY WE ARE STILL WITHIN TO PRICE RANGE QUOTED

CONTINUED NEXT SHEET -



LEAD TIME – approximately 6 weeks after receipt of order. During summer time that may extend due to busy time of season

General Notes:

Sales/Use taxes are INCLUDED in above bid amount.

Payment and Performance Bonds are NOT INCLUDED in the above price. Add 1% for our standard bond form. If alternate bond forms are required there may be an additional cost and the forms will be subject to approval by our bonding company.

Materials stored at owner or GC's request will incur storage fees and handling charges.

All electrical service requirements, including conduit, wiring and/or final hook which may be required shall be provided by electrical subcontractor.

Hoisting for non-ground floor access, unless specifically indicated above is not included.

Permits, if required, are not included and shall be provided by others at others expense.

Flooring -- Concrete slab must be level to 1/8" in a 10' radius and dry to 4.5# per 1,000 Sq.Ft. as tested by Calcium Chloride dry crystal testing methods. All slab prep work, including leveling, and associated cost is by others. Moisture test results must be provided to SSE prior to scheduling of crew to jobsite by others and at others expense. Thresholds, reducers, base and removal/reinstallation of anything on the floor (i.e. bleachers or floor inserts) which may be required are excluded unless specifically included above.

For Wood flooring contracts only; GC shall provide subcontractor with electrical service for floor sanders – 208 v./3phase/100 amps.