



**DeKalb County Department of Planning & Sustainability**

**330 Ponce De Leon Avenue, Suite 300**

**Decatur, GA 30030**

**(404) 371-2155 / [www.dekalbcountyga.gov/planning](http://www.dekalbcountyga.gov/planning)**

**Planning Commission Hearing Date: January 5, 2023**  
**Board of Commissioners Hearing Date: January 26, 2023**

**STAFF ANALYSIS**

**Case No.:** SLUP-22-1246038 **Agenda #:** D7

**Location/Address:** The southeast quadrant of Lawrenceville Highway and Jordan Lane, approximately 415feet north of DeKalb Industrial Way at 1849 Lawrenceville Highway in Decatur, Georgia. **Commission District:** 4 **Super District:** 6

**Parcel ID(s):** 18 063 03 027

**Request:** To request a Special Land Use Permit (SLUP) to allow a drive-through car wash facility in the C-1 (Local Commercial) zoning district.

**Property Owner(s):** Karimshah Inc, Sadruddin Ashiq Ali

**Applicant/Agent:** ModWash LLC c/o Battle Law P.C.

**Acreage:** 1.28

**Surrounding Properties:** Surrounding properties include an auto-broker and multi-family apartments across Jordan Lane to the north; single-family detached homes to the northwest across Lawrenceville Highway; wholesale and medical office uses to the south; a parking lot and a vacant property to the east; and retail and restaurant uses to the west across Lawrenceville Highway.

**Comprehensive Plan:** Town Center (TC) Consistent  Inconsistent

<b>Proposed Density:</b> NA	<b>Existing Density:</b> N.A.
<b>Proposed Units:</b> Drive-through Car Wash	<b>Existing Units:</b> Vacant building
<b>Proposed Lot Coverage:</b> NA	<b>Existing Lot Coverage:</b> N.A.

**STAFF RECOMMENDATION: DENIAL**

The applicant is requesting a Special Land Use Permit (SLUP) to allow a drive-through car wash facility in the C-1 zoning district. There is a companion case to modify the current zoning conditions which restrict the use to retail and office to allow a drive-through car wash facility (See CZ 22 1245934). This case was deferred from the November agenda cycle (the Planning Commission recommended Denial of this case at their November public hearing). Car wash cleaning chemicals can potentially run off into nearby storm drains and degrade water quality. The applicant submitted documentation showing compliance with Section 4.2.13.B (Supplemental Regulations for Car Washes) of the Zoning Ordinance which requires that *wastewater from all auto wash services shall be pre-treated in accordance with watershed maintenance standards prior to being drained into public sanitary sewer or into any stormwater structure as may be approved by DeKalb County Watershed Management Department*. The Watershed Management Department has reviewed the applicant's information and indicated that Drive-through carwashes are not required to apply for Industrial Discharge permit, however, they are required to follow the discharge limits and regulations and install Oil/water/sand/grit separators when necessary. At the time of this writing it is not known if the applicant's information is in compliance with these county regulations.

The site is located within a Town Center (TC) Character Area designated by the *DeKalb County 2035 Comprehensive Plan*. Moreover, the subject property is included in the *Medline LCI Plan* study area, but it doesn't provide a definitive recommendation regarding use of the site. A drive-through car wash does not meet the intent and vision of the TC Character Area calling for a pedestrian community focused within a high density mix of residential, office, and commercial uses. Additionally, the proposed auto-oriented drive-through is not consistent with the following policies and strategies of the TC Character Area of the 2035 Comprehensive Plan: 1. Promote new and redevelopment at or near activity centers as a means of reducing vehicle miles traveled (VMT) (TC Land Use "VMT" Policy, page 94); and 2. Design shall be pedestrian oriented with walkable connections between different uses (site plan shows one row of parking in front of the building (TC Land Use "Pedestrian Oriented Design" Policy, page 94). The LCI Plan does not provide exclusions to provide for pedestrian community uses based on where the use is located in the study area. Regardless of existing and proposed residential densities in the TC Character Area, the goal of TC is to have residents walk more than drive. Since the proposed drive-through land use is inherently inconsistent with the pedestrian community intent of the TC Character Area, additional landscaping or site enhancements will not change this issue. Additionally, more information is needed to verify compliance with stormwater management as the conceptual plan does not indicate location of stormwater facilities (see attached interdepartmental comments from Land Development Division of Public Works). Therefore, it is the recommendation of the Planning and Sustainability Department that the SLUP request to allow a drive-through car wash on the subject site be, respectfully, "Denied".



DEKALB COUNTY GOVERNMENT  
PLANNING DEPARTMENT  
DISTRIBUTION FORM

**NOTE: PLEASE RETURN ALL COMMENTS VIA EMAIL OR FAX TO EXPEDITE THE PROCESS TO MICHELLE ALEXANDER [mmalexander@dekalbcountyga.gov](mailto:mmalexander@dekalbcountyga.gov) AND/OR LASONDRA HILL [lahill@dekalbcountyga.gov](mailto:lahill@dekalbcountyga.gov)**

COMMENTS FORM:  
PUBLIC WORKS WATER AND SEWER

Case No.: SLUP-22-1246038  
Parcel I.D. #: 18-063-03-027  
Address: 1849 LAWRENCEVILLE HWY  
DECATUR, GA 30033

WATER:

Size of existing water main: 12" DI (adequate/inadequate)  
Distance from property to nearest main: adjacent  
Size of line required, if inadequate: unknown

SEWER:

Outfall Servicing Project: South Fork Peachtree Creek  
Is sewer adjacent to property: Yes  No  If no, distance to nearest line: \_\_\_\_\_  
Water Treatment Facility: Atlanta ( ) adequate ( ) inadequate  
Sewage Capacity: 40 (MGPD) Current Flow: 36 (MGPD)

COMMENTS:


Signature: Yola Lewis

10/17/2022

To: Ms. Madolyn Spann, Planning Manager  
Mr. John Reid, Senior Planner  
From: Ryan Cira, Environmental Health Manager  
Cc: Alan Gaines, Technical Services Manager  
Re: Rezone Application Review

General Comments:

DeKalb County Health Regulations prohibit use of on-site sewage disposal systems for

- multiple dwellings
- food service establishments
- hotels and motels
- commercial laundries
- funeral homes
- schools
- nursing care facilities
- personal care homes with more than six (6) clients
- child or adult day care facilities with more than six (6) clients
- residential facilities containing food service establishments

If proposal will use on-site sewage disposal, please contact the Land Use Section (404) 508-7900.

Any proposal, which will alter wastewater flow to an on-site sewage disposal system, must be reviewed by this office prior to construction.

This office must approve any proposed food service operation or swimming pool prior to starting construction.

Public health recommends the inclusion of sidewalks to continue a preexisting sidewalk network or begin a new sidewalk network. Sidewalks can provide safe and convenient pedestrian access to a community-oriented facility and access to adjacent facilities and neighborhoods.

For a public transportation route, there shall be a 5ft. sidewalk with a buffer between the sidewalk and the road. There shall be enough space next to sidewalk for bus shelter's concrete pad installation.

Since DeKalb County is classified as a Zone 1 radon county, this office recommends the use of radon resistant construction.

# DeKalb County Board of Health

404.508.7900 • www.dekalbhealth.net

10/17/2022

---

---

N1 2022-2326

TA-22-124621

County-wide

Amendment

- Please review general comments.

---

---

N2 2022-2252

SLUP-22-1246038 18-063-03-027

1849 Lawrenceville Hwy, Decatur, GA 30033

Amendment

- Please review general comments.

---

---

N3 2022-2253

Z-22-1245936 18-116-04-008

1251 Robinwood Road, Decatur, GA 30033

Amendment

- Please review general comments.

---

---

N4 2022-2254

CZ-22-1246039 15-251-01-028

3458,3468, & 3478 Mountain Drive, Decatur, GA 30032

Amendment

- Please review general comments

## Zoning Comments – October 2022

- N1.** No package to review.
- N2. 1845 Lawrenceville Hwy.** Lawrenceville Hwy is a state route. GDOT review and approval required prior to permitting. Lawrenceville Hwy is classified as a major arterial. Requires a right of way dedication of 50 feet from centerline OR such that all public infrastructure is within right of way, whichever greater. Add ADA Ramps and a pedestrian crossing across Jordan Lane. Requires a 5-foot landscape strip with a 10 foot multi-use path. No poles may remain within the limits of the path. Requires pedestrian scale streetlights. Jordan Lane is classified as a local road. Requires a right of way dedication of 27.5 feet from centerline OR such that all public infrastructure is within right of way, whichever greater. Requires 12-foot travel lane from centerline with curb and gutter. Requires a 5-foot landscape strip with a 5-foot sidewalk. Requires pedestrian scale streetlights. No poles may remain within the limits of the sidewalk. Driveway on Jordan Lane cannot be relocated without Transportation approval- proposed location acceptable.
- N3. 1251 Robinwood Rd.** Build 5 foot sidewalks in front of the subject property and extend to Lawrenceville Hwy within the current right of way. Robinwood Rd is classified as a local road. Requires a right of way dedication of 27.5 feet from centerline OR such that all public infrastructure is within right of way, whichever greater. Requires 12 foot travel lane from centerline with curb and gutter. Requires a 5 foot landscape strip with a 5 foot sidewalk on right of way. Requires pedestrian scale streetlights. Street parking within the right of way must be approved by Roads & Drainage prior to permitting. No poles may remain within the limits of the sidewalk. Interior streets/alleys must be private.
- N4. 3458 Mountain Drive.** Mountain Drive is a state route and requires GDOT review and approval prior to permitting. Requires traffic study to determine required number of lanes and queue lengths at entrances. The study will also determine the need for left turn lanes into the development. Mountain Drive is classified as a collector road. Requires a right of way dedication of 35 from centerline OR such that all public infrastructure is within right of way, whichever greater. Requires a 5 foot landscape strip with a 10 foot multi-use path. No poles may remain within the limits of the path. Requires pedestrian scale streetlights. Speed Limit is 45 mph (per plans). Watch minimum driveway separation spacing in Sec 14-200(6). Speed Limits between 36 to 45mph requires 245 feet of separation between driveways. Developments with 151-300 residential units require 3 access points (Land development Code Sec 14-200(5).) Suggest that if you are seeking a variance that you do it within the zoning process. Interior street must be private.
- N5. 6168 Marbut Rd.** No parking allowed on Marbut Road.
- N6/N7. 2179 Bouldercrest Road.** Bouldercrest Road is classified as a major arterial. Requires a right of way dedication of 50 from centerline OR such that all public infrastructure is within right of way, whichever greater. Replace curbing along property frontage. Requires a 5 foot landscape strip with a 10 foot multituse path. No poles may remain within the limits of the path. Requires pedestrian scale streetlights. No Parking allowed within the right of way.
- N8. 3507 Memorial Drive.** Memorial Drive is a state route. GDOT review and approval required prior to permitting. No comment. Based on the plan, this site it interior to the property and not adjacent to a right of way.

- N9. 311 South Howard St.** (They have the wrong address on the application. It is 211 South Howard Street.) Memorial Drive is a state route within the City of Atlanta. Both agencies will have to review and approve the requirements prior to permitting. For DeKalb: Memorial Drive requires a right of way dedication of 50 foot from centerline OR such that all public infrastructure is within right of way, whichever greater. Requires a 5 foot landscape strip with a 10 foot mulituse path. No poles may remain within the limits of the path. Requires pedestrian scale streetlights. DeKalb Transportation will defer to the City of Atlanta comments for right of way improvements. South Howard St is classified as a collector street. South Howard Street requires a right of way dedication of 35 feet from centerline OR such that all public infrastructure is within right of way, whichever greater. Requires a 5 foot landscape strip with a 10 foot mulituse path. No poles may remain within the limits of the path. Requires pedestrian scale streetlights. Access point must remain at the southern property line on South Howard St. Interior private alley (instead of a shared drive for permitting) must be private. Shared drives not allowed for 6 lots, private alley in this case is allowed.
- N10. 1347 Bermuda Road.** By Code- shared driveways can only be for 2 lots. A variance will be necessary to have 6 lots on a shared driveway. Suggestion: widen to 24 feet and make it a private road. Bermuda Road is classified as a collector road. requires a right of way dedication of 35 from centerline OR such that all public infrastructure is within right of way, whichever greater. Requires a 5 foot landscape strip with a 10 foot mulituse path. No poles may remain within the limits of the path. Requires pedestrian scale streetlights. Watch minimum separation of drives/roads in section 14-200(6) based on the speed limit of the road.
- N11. 8067 Rockbridge Road.** No Access on The Trace. Rockbridge Road is classified as a major arterial. Requires a right of way dedication of 50 feet from centerline OR such that all public infrastructure is within right of way, whichever greater. Requires a 5 foot landscape strip with a 10 foot mulituse path. No poles may remain within the limits of the path. Requires pedestrian scale streetlights. The Trace is classified as a local road. Requires a right of way dedication of 27.5 feet from centerline OR such that all public infrastructure is within right of way, whichever greater. Requires a 5 foot landscape strip with a 5 foot sidewalk path. No poles may remain within the limits of the sidewalk. Requires pedestrian scale streetlights. This property is within the interior of a curve. Intersection sight distance exiting the property (based on AASHTO guidance and sealed by a professional engineer) must be met prior to permitting. Guardrail resign must also take place by a professional engineer along the Rockbridge frontage.
- N12. 1065 Fayetteville Rd.** Fayetteville Road is classified as a collector road. Requires a right of way dedication of 35 feet from centerline OR such that all public infrastructure is within right of way, whichever greater. Requires a 5 foot landscape strip with a 10 foot mulituse path. No poles may remain within the limits of the path. Requires pedestrian scale streetlights. Graham Circle is classified as a local road. Requires a right of way dedication of 27.5 feet from centerline OR such that all public infrastructure is within right of way, whichever greater. Requires a 12 foot travel lane from centerline of road. Requires a 5 foot landscape strip with a 5 foot sidewalk path. No poles may remain within the limits of the sidewalk. Requires pedestrian scale streetlights. Interior streets are shown on site plan as private. If they become public: Requires a right of way dedication of 55 feet. Requires a 5 foot landscape strip with a 6 foot sidewalk. No poles may remain within the limits of the sidewalk. Requires pedestrian scale streetlights.
- N13. 2255, 3375, 3395 Northeast Expressway.** All access is from GDOT right of way. GDOT review and permits required. Further discussions required around the Peachtree Greenway Trail connection. All public infrastructure must be on right of way.
- N14. 1602 Scott Blvd.** Scott Blvd is a state route. GDOT review and approval required prior to permitting. Scott Blvd is classified as a major arterial. Requires a right of way dedication of 50 feet from centerline OR such that all public infrastructure is within right of way, whichever greater. Requires a 5 foot landscape strip with a 10 foot mulituse path. Extend Path to and along Blackmon Drive frontage. No poles may remain within the limits of the path. Requires pedestrian scale streetlights. All interior streets to be private. No access allowed on Blackmon Drive Right in right out only allowed on Scott Blvd- with proper design to prohibit restricted movements.
- N15. 2739 Craigie Ave.** No comment.
- N16. 1259 Sheppard Ct.** No comment.

**N17/N18.** Not in package to review.

**N19.** No comment.





## DEKALB COUNTY GOVERNMENT PLANNING DEPARTMENT DISTRIBUTION FORM

The following areas below may warrant comments from the Development Division. Please respond accordingly as the issues relate to the proposed request and the site plan enclosed as it relates to Chapter 14. You may address applicable disciplines.

### DEVELOPMENT ANALYSIS:

- **Storm Water Management**

Compliance with the Georgia Stormwater Management Manual, DeKalb County Code of Ordinances 14-40 for Stormwater Management and 14-42 for Storm Water Quality Control (sections have been amended recently; please request the amended chapter), to include Runoff Reduction Volume where applicable is required as a condition of land development permit approval. Use Volume Three of the G.S.M.M. for best maintenance practices. Use the NOAA Atlas 14 Point Precipitation Data set specific to the site. Recommend Low Impact Development features/ Green Infrastructure be included in the proposed site design to protect as much as practicable the statewaters and special flood hazard areas.

Conceptual plan doesn't indicate the location of the stormwater management facility. Location of stormwater management shall be shown or compliance with the County stormwater management regulations shall be addressed.

The county codes require the hydrology study to model the existing conditions as wooded.

Additional consideration must be given to the 10% downstream analysis. The proposed development seems to be for a carwash; carwash is considered to be a stormwater hotspot

- **Flood Hazard Area/Wetlands**

The presence of FEMA Flood Hazard Area was not indicated in the County G.I.S. mapping records for the site; and should be noted in the plans at the time of any land development permit application. Encroachment of flood hazard areas require compliance with Article IV of Chapter 14 and FEMA floodplain regulations

- **Landscaping/Tree Preservation**

Landscaping and tree preservation plans for any building, or parking lot must comply with DeKalb County Code of Ordinances 14-39 as well as Chapter 27 Article 5 and are subject to approval from the County Arborist.

- **Tributary Buffer**

State water buffer was not reflected in the G.I.S. records for the site. Typical state waters buffer have a 75' undisturbed stream buffer and land development within the undisturbed creek buffer is prohibited without a variance per DeKalb County Code of Ordinances 14-44.1.



**DEKALB COUNTY GOVERNMENT  
PLANNING DEPARTMENT  
DISTRIBUTION FORM**

N-2

**NOTE: PLEASE RETURN ALL COMMENTS VIA EMAIL OR FAX TO EXPEDITE THE PROCESS TO MICHELLE ALEXANDER [mmalexander@dekalbcountyga.gov](mailto:mmalexander@dekalbcountyga.gov) AND/OR LASONDRA HILL [lahill@dekalbcountyga.gov](mailto:lahill@dekalbcountyga.gov)**

**COMMENTS FORM:  
PUBLIC WORKS TRAFFIC ENGINEERING**

Case No.: SLUP-22-1246038 Parcel I.D. #: 18-063-03-027

Address: 1849  
LAWRENCEVILLE Hwy  
DEKALB GA 30033

Adjacent Roadway (s):

(classification)	(classification)

Capacity (TPD) \_\_\_\_\_  
Latest Count (TPD) \_\_\_\_\_  
Hourly Capacity (VPH) \_\_\_\_\_  
Peak Hour Volume (VPH) \_\_\_\_\_  
Existing number of traffic lanes \_\_\_\_\_  
Existing right of way width \_\_\_\_\_  
Proposed number of traffic lanes \_\_\_\_\_  
Proposed right of way width \_\_\_\_\_

Capacity (TPD) \_\_\_\_\_  
Latest Count (TPD) \_\_\_\_\_  
Hourly Capacity (VPH) \_\_\_\_\_  
Peak Hour Volume (VPH) \_\_\_\_\_  
Existing number of traffic lanes \_\_\_\_\_  
Existing right of way width \_\_\_\_\_  
Proposed number of traffic lanes \_\_\_\_\_  
Proposed right of way width \_\_\_\_\_

Please provide additional information relating to the following statement.


According to studies conducted by the Institute of Traffic Engineers (ITE) 6/7<sup>TH</sup> Edition (whichever is applicable), churches generate an average of fifteen (15) vehicle trip end (VTE) per 1,000 square feet of floor area, with an eight (8%) percent peak hour factor. Based on the above formula, the \_\_\_\_\_ square foot place of worship building would generate \_\_\_\_\_ vehicle trip ends, with approximately \_\_\_\_\_ peak hour vehicle trip ends.


Single Family residence, on the other hand, would generate ten (10) VTE's per day per dwelling unit, with a ten (10%) percent peak hour factor. Based on the above referenced formula, the \_\_\_\_\_ (Single Family Residential) District designation which allows a maximum of \_\_\_\_\_ units per acres, and the given fact that the project site is approximately \_\_\_\_\_ acres in land area, \_\_\_\_\_ daily vehicle trip end, and \_\_\_\_\_ peak hour vehicle trip end would be generated with residential development of the parcel.


COMMENTS:


Plans and field reviewed. Found nothing that would disrupt traffic flow or pattern change.

Signature: [Signature] David M. Ross









NOTATION: CONTRACTOR TO PROVIDE RECONSTRUCTION AND IMPROVEMENTS TO EXISTING PLAN AND FROM SANITARY PRESS TO CORRECT SECTION CORNER (IT TO BE SUBMITTED TO THE PROJECT ANALYST AND DESIGNATOR BEFORE ANY APPROVAL) (SEE SECTION 1.1 FOR CONSTRUCTION AND UTILITY)

DEPARTMENT OF PLANNING & SUSTAINABILITY

**SPECIAL LAND USE PERMIT APPLICATION**

Amendments will not be accepted after 5 working days after the filing date.

Date Received: \_\_\_\_\_ Application No.: \_\_\_\_\_

APPLICANT NAME: ModWash, LLC c/o Battle Law, P.C.

Daytime Phone #: 404.601.7616 Fax #: 404.745.0045

Mailing Address: 3562 Habersham at Northlake Building J, Suite 100 Tucker, Georgia 30084

E-mail: \_\_\_\_\_

OWNER NAME: Karimshah Inc. Sadruddin Ashiq Ali (If more than one owner, attach contact information for each owner)

Daytime Phone #: \_\_\_\_\_ Fax #: \_\_\_\_\_

Mailing Address: 1845 Lawrenceville Highway, Decatur, Georgia 30033

E-mail: \_\_\_\_\_

SUBJECT PROPERTY ADDRESS OR LOCATION: 1849 Lawrenceville Highway

Decatur, DeKalb County, GA, 30033

District(s): 18 Land Lot(s): 063 Block(s): 03 Parcel(s): 18 063 03 027

Acreage or Square Feet: 1.28 Commission District(s): 4 & 6 Existing Zoning: C-1

Proposed Special Land Use (SLUP): Drive Thru

I hereby authorize the staff of the Planning and Development Department to inspect the property that is the subject of this application.

Owner: \_\_\_\_\_ Agent:  Signature of Applicant: By: [Signature]  
(Check One) Authorized Rep.

Printed Name of Applicant: ModWash, LLC c/o Battle Law, P.C.

Notary Signature and Seal:

[Signature]







DeKalb County  
GEORGIA

404.371.2155 (o)  
404.371.4556 (f)  
DeKalbCountyGa.gov

178 Sams Street  
Decatur, GA 30030

DEPARTMENT OF PLANNING & SUSTAINABILITY

**SPECIAL LAND USE PERMIT APPLICATION AUTHORIZATION**

The property owner should complete this form or a similar, signed and notarized form if the individual who will file the application with the County is not the property owner.


Date: \_\_\_\_\_


TO WHOM IT MAY CONCERN:

(I) (WE), \_\_\_\_\_ Karimshah Inc.  
Name of Owner(s)

being (owner) (owners) of the subject property described below or attached hereby delegating to  
\_\_\_\_\_ ModWash, LLC c/o Battle Law, P.C.  
Name of Applicant or Agent

to file an application on (my) (our) behalf.

  
Notary Public

Karimshah Inc  
  
Owner



\_\_\_\_\_  
Notary Public Owner

\_\_\_\_\_  
Notary Public Owner

\_\_\_\_\_  
Notary Public Owner

Chief Executive Officer  
Michael Thurmond

DEPARTMENT OF PLANNING & SUSTAINABILITY

Director  
Andrew A. Baker, AICP

**PRE-APPLICATION FORM**  
**REZONE, SPECIAL LAND USE PERMIT, MODIFICATION, AND LAND USE**  
**(Required prior to filing application: signed copy of this form must be submitted at filing)**

Applicant Name:  Battle Law  Phone: : 404-601-7616 ext 6\_\_\_\_\_ Email: mlb@Battlelawpc.com

Property Address:  1849 Lawrenceville Hwy

Tax Parcel ID:  18 063 03 027-  Comm. District(s):  4 & 6  Acreage:  1.26

Existing Use:  vacant lot  Proposed Use  Car Wash (fancy express car wash)

Supplemental Regs:  X  Sec 4.2.13 \_\_\_\_\_ Overlay District:  NA  DRI:  NA

**Rezoning:** Yes \_\_\_\_\_ No  X

Existing Zoning:  C-1 with conditions per CZ-06-1241

Proposed Zoning:  NA

Square Footage/Number of Units: \_\_\_\_\_

Rezoning Request:  NA

**Land Use Plan Amendment:** Yes \_\_\_\_\_ No  X

Existing Land Use:  SUB  Proposed Land Use:  CRC  Consistent \_\_\_\_\_  
Inconsistent \_\_\_\_\_

**Special Land Use Permit:** Yes \_\_\_\_\_ No  X  Article Number(s) 27-  
\_\_\_\_\_

Special Land Use Request(s) \_\_\_\_\_

**Major Modification:**

Existing Case Number(s):  CZ-06-1241

Condition(s) to be modified:

\_\_\_\_\_ Condition #1 pertaining to limit use to office and retail so can operate a car wash. Condition #5 require that access to Jordan Road to be closed but it never was...applicant would like to remain open.

DEPARTMENT OF PLANNING & SUSTAINABILITY

WHAT TO KNOW BEFORE YOU FILE YOUR APPLICATION

Pre-submittal Community Meeting:  Review Calendar Dates:  PC: 09/01/22\*  
BOC:  09/29/22\*\* Letter of Intent:  Impact Analysis:  Owner Authorization(s):   
Campaign Disclosure:  Zoning Conditions:  Community Council Meeting:  08/16/22  
Public Notice, Signs:  (Applicant must pick up and post and/or will be done by Staff) Tree  
Survey, Conservation: \_\_\_\_\_ Land Disturbance Permit (LDP):  Sketch Plat:   
Bldg. Permits:  Fire Inspection:  Business License:  State License:  
\_\_\_\_\_ Lighting Plan: \_\_\_\_\_ Tent Permit: \_\_\_\_\_ Submittal Format: NO STAPLES, NO BINDERS  
PLEASE

**\*Land Use Amendment applications only heard in March and September and take priority over other cases; if cap is hit then may have to go to November agenda.**

**\*Deadline for hosting pre-community meeting with 15 days notice for September 2022 agenda cycle would be 06/29/22**

**\*\*Filing Deadline for application is 06/30/22**

Review of Site Plan

Density:  Density Bonuses:  Mix of Uses: \_\_\_\_\_ Open Space:   
Enhanced Open Space:  Setbacks: front  sides  side corner \_\_\_\_\_ rear   
Lot Size:  Frontage:  Street Widths:  Landscape Strips:   
Buffers: \_\_\_\_\_ Parking Lot Landscaping: \_\_\_\_\_ Parking - Auto:  Parking - Bicycle:  
 Screening:  Streetscapes:  Sidewalks:  Fencing/Walls:   
Bldg. Height:  Bldg. Orientation: \_\_\_\_\_ Bldg. Separation: \_\_\_\_\_ Bldg. Materials:  Roofs:  
 Fenestration:  Façade Design:  Garages:  Pedestrian Plan:   
Perimeter Landscape Strip: \_\_\_\_\_  
Possible Variances: \_\_\_\_\_

**DEPARTMENT OF PLANNING & SUSTAINABILITY**

Comments: \_\_. \_\_ Applicant will need to justify how the proposed modification to zoning conditions to allow a car wash is consistent with pedestrian-oriented use and connectivity policies of the Town Center (TC) Character Area as well as consistent with adjacent and surrounding uses. Applicant will need to demonstrate compliance with C-1 zoning requirements and the Supplemental Regulations for car washes (Sec 4.2.13). Show compliance with C-1 requirements, including but not limited to required parking, transitional buffers, minimum open space, maximum building height, streetscape improvements, and required density bonus provisions (if applicable), etc. The applicant is encouraged to discuss possible transportation improvements that may be required (if the rezoning is approved by the Board of Commissioners) with the county Transportation Department. The applicant is encouraged to contact Land Development Division of Public Works regarding required storm water management, floodplain, and stream buffer issues.

**This only a preliminary review and is not a complete list of zoning requirements, a final and complete review will be done upon official submission of a rezoning application and concept plan.**

Planner: John Reid Date 05/05/22

Filing Fees

<b>REZONING:</b>	RE, RLG, R-100, R-85, R-75, R-60, MHP, RSM, MR-1	\$500.00
	RNC, MR-2, HR-1, HR-2, HR-3, MU-1, MU-2, MU-3, MU-4, MU-5	\$750.00
	OI, OD, OIT, NS, C1, C2, M, M2	\$750.00
<b>LAND USE MAP AMENDMENT</b>		\$500.00
<b>SPECIAL LAND USE PERMIT</b>		\$400.00



## Battle Law

3562 Habersham at Northlake, Bldg. J, Ste 100  
Tucker, Georgia 30084

### Zoom Instructions:

Go to <https://www.battlelawpc.com> . On the Home page, please click on “Projects”, then choose “DeKalb County”. Scroll down to the correct “Project Title” and click on “Join Meeting” under the correct meeting date. To join by phone, please dial (646) 558-8656 and enter the Meeting ID and Passcode provided on the website.

We encourage you to come out and participate!

*\*\*Please Note: This meeting is hosted solely by Battle Law, P.C.\*\**

For More Information Contact  
Brittney Butler at:  
Phone: 404-601-7616 ext. 7  
Fax: 404-745-0045  
Email: [btb@battlelawpc.com](mailto:btb@battlelawpc.com)

# CHANGE OF APPROVED CONDITIONS TO ALLOW FOR THE DEVELOPMENT OF AN AUTOMATED CAR WASH

You are invited to a Zoom meeting.

**Project Title: 1849 Lawrenceville  
Highway**

**When: Tuesday, May 24, 2022**

**Time: 6:00 PM Eastern (US and Canada)**

**Register in advance for this meeting:**

**<https://www.battlelawpc.com>**



**PROPOSED LOCATION(S):**

**1849 Lawrenceville Highway  
Decatur, Georgia 30033  
Parcel Number**



# Battle Law

3562 Habersham at Northlake, Bldg. J, Ste 100  
Tucker, Georgia 30084

PLEASE  
PLACE  
STAMP  
HERE

«Name»

«Address»

«City», «State» «Zip»

After recording please return to:  
Zain N. Kapadia, Esq.  
Kapadia & Naik, Attorney at Law, LLC  
7000 Central Pkwy, Suite 1100  
Atlanta, Georgia 30328  
DeKalb County Tax Parcel ID: 18 063 03 027

---

**STATE OF GEORGIA**

**COUNTY OF GWINNETT**

**EXECUTOR'S DEED**

**THIS INDENTURE** is made this 13th day of April, 2022, by and between **AYAZ ALI**, not individually, but as Independent Executor under the Last Will and Testament of Ashiq Ali Vansi a/k/a Ashiq Ali Sadruddin, late of Gwinnett County, Georgia (hereinafter referred to as the "Deceased"), (the aforesaid, as party of the first part, hereinafter called "Grantor"), and **AYAZ ALI**, a Georgia resident, as party of the second part, hereinafter called Grantee (the terms, "Grantor" and "Grantee" to include their respective heirs, successors, successors-in-title, heirs, executors, administrators, legal representatives, and assigns where the context requires or permits).

**WITNESSETH:**

Grantor, acting under and by virtue of the power and authority contained in the will of the Deceased, it having been duly probated in solemn form on October 26, 2021, in Gwinnett County, Georgia, and subsequently amended to correct the omission of the Deceased's previous surname, and recorded as part of the records of the Probate Court of Gwinnett County, Georgia, on November 3, 2021, **FOR AND IN CONSIDERATION** of the sum of Ten Dollars (\$10.00) in hand paid to Grantor by Grantee at and before the execution, sealing and delivery hereof, and other good and valuable consideration, the receipt and sufficiency of which are hereby acknowledged, Grantor has granted, bargained, sold, aliened, conveyed and confirmed, and by these presents does grant, bargain, sell, alien, convey and confirm unto Grantee, and the successors, legal representatives and assigns of Grantee, all that certain real property lying and being in DeKalb County, Georgia, being more particularly described on **Exhibit "A"**, attached hereto and incorporated herein by reference, subject only to those matters set forth on **Exhibit "B"**.

**TO HAVE AND TO HOLD** the said tract or parcel of land unto the said Grantee, its successors and assigns, so that neither the said Grantor nor its heirs, successors or assigns, nor any person claiming under it shall at any time, claim or demand any right, title or interest to the aforesaid described tract or parcel of land or its appurtenances.

**{SIGNATURE APPEARS ON THE FOLLOWING PAGE}**

IN WITNESS WHEREOF, Grantor has signed and sealed this Executor's Deed as of the day and year first above written.

Signed, sealed and delivered in the presence of:

Munira

Witness

Print Name: Munira Goawalla.

[Signature]

Notary Public

[Signature]

(SEAL)

AYAZ ALI, not Individually, but as Independent Executor under the Last Will and Testament of Ashiq Ali Vansi a/k/a Ashiq Ali Sadruddin

Commission Expires: 2/16/2025  
(AFFIX NOTARY SEAL)



4/13/2022



**EXHIBIT "A"**  
**LEGAL DESCRIPTION**

All That Tract of parcel of land lying and being in Land Lot 63 of the 18<sup>th</sup> District, DeKalb County, Georgia, being more particularly described as follows:

Beginning at a concrete right-of-way monument found at the intersection of the easterly right-of-way (100 feet from centerline) of Lawrenceville Highway and the southerly right-of-way (30 feet from centerline) of Scottdale Road; thence South 54 degrees 25 minutes 09 seconds East 231.28 feet along the southerly right-of-way of Scottdale Road to a 1/2" rebar set; thence South 35 degrees 56 minutes 27 seconds West 220.94 feet to a 1/2" rebar set; thence North 47 degrees 58 minutes 56 seconds West 275.00 feet to a 1/2" rebar set on the easterly right-of-way (56 feet from centerline) of Lawrenceville Highway; thence North 35 degrees 28 minutes 57 seconds East 130.61 feet along said right-of-way to a concrete right-of-way monument (56 feet from centerline); thence continuing along the easterly right-of-way of Lawrenceville Highway North 64 degrees 19 minutes 14 seconds East 40.27 feet to a concrete right-of-way monument found at (75 feet from centerline of Lawrenceville Highway); thence continuing along the southeasterly right-of-way of Lawrenceville Highway South 85 degrees 06 minutes 28 seconds East 29.17 feet to the Point of Beginning; said tract containing 1.27 acres, all according to a plat of survey prepared by Donald W. Harkleroad & Associates, Inc. dated July 21, 1984.

LESS AND EXCEPT SO MUCH OF SAID PROPERTY AS HAS BEEN USED IN WIDENING ANY RIGHT-OF-WAY OF TAKEN BY CONDEMNATION OR CONVEYED BY DEED.

**EXHIBIT "B"**

**TITLE EXCEPTIONS**

1. Ad valorem real property taxes for the year 2022 not due and payable.
2. Present and future zoning laws, ordinances, resolutions, orders and regulations of all municipal, county, state or federal governments having jurisdiction over the Property and the use of improvements thereon (including any violations thereof).
3. The lien of any unpaid water charges and sewer rents for the year 2022.
4. The lien of all unpaid assessments encumbering the Property on the date hereof.
5. The lien of all unpaid assessments which first encumber the Property subsequent to the date hereof, and installments thereof.
6. All liens and encumbrances resulting from the investigations by and activities of Grantee or its representatives upon the Property prior to the date hereof.
7. Building codes heretofore or hereafter adopted by any public agency (including any violations thereof).
8. All easements, restrictions, and other matters of record.
9. All matters which would be disclosed by an accurate and current survey and inspection of the Property.
10. That certain billboard lease affecting a portion of the Property dated July 22, 1999, with Lamar Companies as tenant.

After recording please return to:  
Zain N. Kapadia, Esq.  
Kapadia & Naik, Attorney at Law, LLC  
7000 Central Pkwy, Suite 1100  
Atlanta, Georgia 30328  
DeKalb County Tax Parcel ID: 18 063 03 027

---

**STATE OF GEORGIA**

**COUNTY OF GWINNETT**

**LIMITED WARRANTY DEED**

**THIS INDENTURE** is made this 13th day of April, 2022, by and between **AYAZ ALI**, a Georgia resident, (the aforesaid, as party of the first part, hereinafter called "Grantor"), and **KARIMSHAH, INC.**, a Georgia corporation, as party of the second part, hereinafter called Grantee (the terms, "Grantor" and "Grantee" to include their respective heirs, successors, successors-in-title, heirs, executors, administrators, legal representatives, and assigns where the context requires or permits).

WITNESSESTH:

**FOR AND IN CONSIDERATION** of the sum of Ten Dollars (\$10.00) in hand paid to Grantor by Grantee at and before the execution, sealing and delivery hereof, and other good and valuable consideration, the receipt and sufficiency of which are hereby acknowledged, Grantor has granted, bargained, sold, aliened, conveyed and confirmed, and by these presents does grant, bargain, sell, alien, convey and confirm unto Grantee, and the successors and assigns of Grantee that certain property located in DeKalb County, Georgia, more particularly described on Exhibit "A" attached hereto and incorporated herein by reference (the "**Property**").

**TO HAVE AND TO HOLD** said Property, together with any and all of the rights, members and appurtenances thereof to the same being, belonging or in anywise appertaining to the only proper use, benefit and behalf of Grantee forever, in fee simple, subject only to those matters set forth on Exhibit "B"; and

**GRANTOR SHALL WARRANT** and forever defend the right and title to said Property unto Grantee, and the successors and assigns of Grantee, against the claims of all persons whomsoever, claiming by, through or under Grantor, but not otherwise.

**IN WITNESS WHEREOF**, Grantor has executed and sealed this indenture, and delivered this indenture to Grantee, the day and year first written above.

**{SIGNATURE APPEARS ON THE FOLLOWING PAGE}**

IN WITNESS WHEREOF, Grantor has signed and sealed this Limited Warranty Deed as of the day and year first above written.

Signed, sealed and delivered in the presence of:

Murica  
Unofficial Witness

[Signature]  
Notary Public

GRANTOR:

AYAZ ALI,  
a Georgia resident

By: [Signature] (SEAL)  
Name: Ayaz Ali

My Commission Expires: 2/16/2025

(NOTARIAL SEAL)



4/13/2022

**EXHIBIT "A"**  
**LEGAL DESCRIPTION**

All That Tract of parcel of land lying and being in Land Lot 63 of the 18<sup>th</sup> District, Dekalb County, Georgia, being more particularly described as follows:

Beginning at a concrete right-of-way monument found at the intersection of the easterly right-of-way (100 feet from centerline) of Lawrenceville Highway and the southerly right-of-way (30 feet from centerline) of Scottdale Road; thence South 54 degrees 25 minutes 09 seconds East 231.28 feet along the southerly right-of-way of Scottdale Road to a 1/2" rebar set; thence South 35 degrees 56 minutes 27 seconds West 220.94 feet to a 1/2" rebar set; thence North 47 degrees 58 minutes 56 seconds West 275.00 feet to a 1/2" rebar set on the easterly right-of-way (56 feet from centerline) of Lawrenceville Highway; thence North 35 degrees 28 minutes 57 seconds East 130.61 feet along said right-of-way to a concrete right-of-way monument (56 feet from centerline); thence continuing along the easterly right-of-way of Lawrenceville Highway North 64 degrees 19 minutes 14 seconds East 40.27 feet to a concrete right-of-way monument found at (75 feet from centerline of Lawrenceville Highway); thence continuing along the southeasterly right-of-way of Lawrenceville Highway South 85 degrees 06 minutes 28 seconds East 29.17 feet to the Point of Beginning; said tract containing 1.27 acres, all according to a plat of survey prepared by Donald W. Harkleroad & Associates, Inc. dated July 21, 1984.

LESS AND EXCEPT SO MUCH OF SAID PROPERTY AS HAS BEEN USED IN WIDENING ANY RIGHT-OF-WAY OF TAKEN BY CONDEMNATION OR CONVEYED BY DEED.

**EXHIBIT "B"**





**TITLE EXCEPTIONS**

1. Ad valorem real property taxes for the year 2022 not due and payable.
2. Present and future zoning laws, ordinances, resolutions, orders and regulations of all municipal, county, state or federal governments having jurisdiction over the Property and the use of improvements thereon (including any violations thereof).
3. The lien of any unpaid water charges and sewer rents for the year 2022.
4. The lien of all unpaid assessments encumbering the Property on the date hereof.
5. The lien of all unpaid assessments which first encumber the Property subsequent to the date hereof, and installments thereof.
6. All liens and encumbrances resulting from the investigations by and activities of Grantee or its representatives upon the Property prior to the date hereof.
7. Building codes heretofore or hereafter adopted by any public agency (including any violations thereof).
8. All easements, restrictions, and other matters of record.
9. All matters which would be disclosed by an accurate and current survey and inspection of the Property.
10. That certain billboard lease affecting a portion of the Property dated July 22, 1999, with Lamar Companies as tenant.

TITLE EXCEPTIONS

FIDELITY NATIONAL TITLE INSURANCE COMPANY DEKALB APARTMENTS INC. TO GEORGIA POWER COMPANY, A CORPORATION, DATED MARCH 18, 1965, FILED FOR RECORD APRIL 27, 1965 AT 3:30 P.M., RECORDED IN DEED BOOK 1981, PAGE 775, AFORESAID RECORDS.

(o) PERMIT FOR ANCHORS, GUY POLES AND WIRES FROM DEKALB APARTMENTS INC. TO GEORGIA POWER COMPANY, A CORPORATION, DATED MARCH 18, 1965, FILED FOR RECORD APRIL 27, 1965 AT 3:30 P.M., RECORDED IN DEED BOOK 1981, PAGE 775, AFORESAID RECORDS.



SURVEY NOTES

- 1) PROPERTY SHOWN HEREON WAS SURVEYED JUNE 16, 2022.
2) THE FIELD DATA UPON WHICH THIS PLAT IS BASED HAS A CLOSURE OF 1" IN 42,734' WITH AN ANGULAR ERROR OF 3.21 SECONDS PER ANGLE POINT AND WAS ADJUSTED USING THE LEAST SQUARES METHOD.
3) A SOKKIA IX TOTAL STATION, CARLSON BRX7 GPS RECEIVER, AND CARLSON SURVEYOR+ DATA COLLECTOR WERE USED FOR FIELD SURVEY MEASUREMENTS.

UTILITY CONTACTS

- WATER DEKALB COUNTY WATER 404-731-3562
GAS ATLANTA GAS LIGHT 470-259-1672
POWER GEORGIA POWER 404-506-6539
COMMUNICATION ATT / D 305-409-1542
COMCAST 912-402-8531
DEKALB COUNTY TRAFFIC 404-297-3947
VERIZON BUSINESS (MCI FACILITIES) 800-624-9675
ZAYO FIBER SOLUTIONS 470-249-5124

LINE TABLE table with columns: LINE, BEARING, DISTANCE. Rows: L1, L2, L3.

LEGAL DESCRIPTION

ALL THAT TRACT OR PARCEL OF LAND LYING AND BEING IN LAND LOT 63, IN THE 18TH DISTRICT, IN DEKALB COUNTY, GEORGIA AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS: COMMENCING AT A CONCRETE RIGHT OF WAY MONUMENT AT THE INTERSECTION OF THE EASTERLY RIGHT OF WAY OF LAWRENCEVILLE HIGHWAY...

SURVEYOR'S CERTIFICATION


THIS PLAT IS A RETRACEMENT OF AN EXISTING PARCEL OR PARCELS OF LAND AND DOES NOT SUBDIVIDE OR CREATE A NEW PARCEL OR MAKE ANY CHANGES TO ANY REAL PROPERTY BOUNDARIES...

ZONING

PER ITEMS 6(A) AND 6(B) OF THE 2021 ALTA/NSPS LAND TITLE SURVEY MINIMUM STANDARD DETAIL REQUIREMENTS, SETBACKS AND OTHER ZONING RESTRICTIONS/REQUIREMENTS CANNOT BE LISTED UNLESS A ZONING REPORT OR LETTER STATING SAID RESTRICTIONS/REQUIREMENTS IS PROVIDED.




Vertical sidebar containing: PREPARED FOR: MODWASH, LLC; LOWERY & ASSOCIATES LAND SURVEYING, LLC; VICINITY MAP; SURVEY NOTES; UTILITY CONTACTS; LEGEND; REVISIONS; and company logo.



SITE DATA		
STREET LOCATION: 1849 LAWRENCEVILLE HWY, DECATUR, GEORGIA		
CURRENT SITE AREA: 1.28 A.C. TOTAL		
CURRENT ZONING: C-1 LOCAL COMMERCIAL (FLUM: TC)		
BUILDING TYPE: NEW 120' CONVEYOR		
ZONING REQUIREMENTS	REQUIRED	PROPOSED
<b>BUILDING SETBACKS</b>		
FRONT	20'	>20'
LEFT	15'	>15'
RIGHT	30'	>30'
REAR	20'	>20'
<b>PARKING (MAX.)</b>		
3 STACKING PER LANE	TBD	18 VAC
3 DRYING PER LANE		7 REGULAR
60 DEGREES	9'x17' (14' AISLE)	12'x20'
90 DEGREES	9'x18' (24' AISLE)	-
FAR (MAX.)	90%	8.2%
MIN. OPEN SPACE	15%	34% (0.44 AC.)

HOURS OF OPERATION 8AM TO 8PM

LINE	BEARING	DISTANCE
L1	N35°05'25"E	138.59'
L2	N64°02'20"E	40.27'
L3	S87°35'26"E	29.17'



DRIVEWAY TO BE REMOVED, NEW CURB TO BE ADDED TO CLOSE DRIVEWAY

NO.	DATE:	DESCRIPTION	REVISIONS
4			
3			
2			
1			




SITE PLAN	
PROJECT NAME:	MODWASH 1849 LAWRENCEVILLE HWY, DECATUR, GEORGIA
CLIENT:	HUTTON 738 CHERRY STREET, CHATTANOOGA, TENNESSEE 37402

PROJECT NO.:	PROJ. MGR.:
DATE:	DRWN. BY:
SCALE:	CHKD. BY:
DRAWING SERIES:	
SITE	
SHEET NO. C-2.0	


TIME PERIOD	LAND USE	ITE LUC	TRIP RATE EQUATION*	QUANTITY (X)	% ENTERING	% EXITING	TRIPS ENTERING	TRIPS EXITING	TOTAL TRIPS
DAILY	AUTOMATED CAR WASH	948	T=116.0(X)	4.4   KSF	50%	50%	255	255	510
PM PEAK-HOUR	AUTOMATED CAR WASH	948	T=14.2(X)	4.4   KSF	50%	50%	32	32	64

\*ITE TRIP GENERATION RATES FOR WEEKDAY AND A.M. PEAK HOUR OF CODE 948 IS NOT AVAILABLE. AN ESTIMATE WAS GENERATED EXTRAPOLATING USING TYPICAL PM PEAK HOUR PERCENTAGES. 10% OF THE DAILY TRIPS WAS ESTIMATED TO OCCUR DURING THE P.M. PEAK HOUR.



DATE





PLANT\_SCHEDULE

TREES	CODE	QTY	BOTANICAL / COMMON NAME	
	IP2	4	Ilex vomitoria 'Pendula' / Weeping Yaupon Holly 7'-8' ht. x 4'-5', 1-1/2" CAL., 30 gal	
	IS	3	Ilex x attenuata 'Savannah' / Savannah Holly 10'-12'; ht. x 4'-6' spd. 3' c.t. 2" cal min.	
	LN1	4	LAGERSTROEMIA INDICA 'NATCHEZ' / NATCHEZ CRAPE MYRTLE 6' Ht. 3 - 5 STEMS, 1" CAL. MIN., 3 LARGEST CANES, 30 GAL.	
	MB	6	Magnolia grandiflora 'Brackens Brown Beauty' / Bracken's Beauty Southern Magnolia 12'-14' ht, x 6'-8' spd. 3" cal.	
	PE3	7	PINUS ELLIOTTI / SLASH PINE 12' - 14' HEIGHT, 5' SPREAD MIN., 3" CAL., B & B	
	OS	7	Quercus shumardii / Shumard Oak 14'-16; ht. x 5'-7' spd. 4" cal min.	
SHRUBS	CODE	QTY	BOTANICAL / COMMON NAME	SPACING
	ID2	76	Ilex cornuta 'Dwarf Burford' / Dwarf Burford Holly36" o.c. 18"-24" ht. x 12"-18" spd., 3 gal.	
	IN	39	Ilex vomitoria 'Nana' / Dwarf Yaupon Holly 36" o.c. 12"-16" ht. x 14"-16" spd., 3 gal.	
	IN2	8	Ilex x 'Nellie R Stevens' / Nellie Stevens Holly 60" o.c. 4'-6' ht, x 3'-4' spd. full specimen	
GROUND COVERS	CODE	QTY	BOTANICAL / COMMON NAME	SPACING
	LM	117	Lantana camara 'Gold Mound' / Gold Mound Lantana 24" o.c. Full 1 gallon pots	
	MC	1,205	Muhlenbergia capillaris / Pink Muhly Grass 24" o.c. 12" - 14" ht. x 10"-14" spd., 1 gallon	
	PV2	590	Panicum virgatum / Switch Grass 36" o.c. Full 1 gallon pots	
	SS	355	Schizachyrium scoparium 'Standing Ovation' / Standing Ovation Little Bluestem 24" o.c. Full 1 gallon pots	

Wildflower Seed Georgia Wildflower mix available at Eaden Brothers, 2099 Brevard Road, Arden, N.C.  
Seed @ 1 lb./12000 s.f.

-All trees planted to meet tree canopy replacement requirements shall meet ANSI Z60.1 Standards for Nursery Stock and all planting shall be done in accordance with current ANSI A300 Standards for Tree Care Operations, ANSI Z133 Safety Standards and industry best management practices, as well as the administrative standards that accompany this Section.  
- Mulch all beds with tan/brown River rock 3/4" x 1-1/2". Install river rock 3" thick with geotextile cloth beneath.

Modwash - Decatur  
Parking lot tree canopy


Code	Qty.	Botanical/Common	Remarks	SF Coverage Ea.	SF Coverage Total
IP2	4	Ilex vomitoria 'Pendula' / Weeping Yaupon Holly	7'-8' ht. x 4'-5', 1-1/2" CAL., 30 gal	150	600
LN1	2	LAGERSTROEMIA INDICA 'NATCHEZ' / NATCHEZ CRAPE MYRTLE	6' Ht. 3 - 5 STEMS, 1" CAL. MIN., 3 LARGEST	150	300
OS	7	Quercus shumardii / Shumard Oak	14'-16; ht. x 5'-7' spd. 4" cal min.	1600	11200
<b>TOTAL</b>				<b>12100</b>	<b>12100</b>

VUA GREEN		TREE COVER	
VUA	25,586 SF	VUA	25,586 SF
%GREEN REQUIRED	x 10%	%REQUIRED	x 45%
-REQUIRED SF	2,558 SF	-COVERAGE REQUIRED	11,514 SF
-PROVIDED SF	5,073 SF	-COVERAGE PROVIDED	12,100 SF

TREES REQUIRED

PERIMETER TREES	Required	Provided
North West 190 lf/40=	5 trees	5 trees
North East 231 lf/40=	6 trees	6 trees
INTERIOR TREES		
PARKING SPACES 24/8 = 3 trees	9 trees	

IRRIGATION NOTE:  
IRRIGATION CONTRACTOR TO PROVIDE A DESIGN FOR AN IRRIGATION SYSTEM SEPARATING PLANTING BEDS FROM LAWN AREA. PRIOR TO CONSTRUCTION, DESIGN IS TO BE SUBMITTED TO THE PROJECT LANDSCAPE DESIGNER FOR REVIEW AND APPROVAL. WHERE POSSIBLE, DRIP IRRIGATION AND OTHER WATER CONSERVATION TECHNIQUES SUCH AS RAIN SENSORS SHALL BE IMPLEMENTED. CONTRACTOR TO VERIFY MAXIMUM ON SITE DYNAMIC WATER PRESSURE AVAILABLE MEASURED IN PSI. PRESSURE REDUCING DEVICES OR BOOSTER PUMPS SHALL BE PROVIDED TO MEET SYSTEM PRESSURE REQUIREMENTS. DESIGN TO SHOW ALL VALVES, PIPING, HEADS, BACKFLOW PREVENTION, METERS, CONTROLLERS, AND SLEEVES WITHIN HARDSCAPE AREAS.




NO.	DATE:	DESCRIPTION
4		
3		
2		
1		



DRAWING TITLE:	LANDSCAPE PLAN
	PROJECT NAME: MODWASH 1849 LAWRENCEVILLE HWY., DECATUR, GEORGIA
CLIENT:	HUTTON 736 CHERRY STREET, CHATTANOOGA, TENNESSEE 37402

PROJECT NO.:	PROJ. MGR.:
DATE: 06.29.22	DRWN. BY: JDV
SCALE: AS NOTED	CHKD. BY: LW
DRAWING SERIES: LANDSCAPE	
SHEET NO. L-1.0	

DATE




**LINE TABLE**

LINE	BEARING	DISTANCE
L1	N35°05'25"E	138.59'
L2	N64°02'20"E	40.27'
L3	S87°35'26"E	29.17'

- LIGHTING NOTES:**
1. LIGHTING IN ALL ZONING DISTRICTS SHALL BE ESTABLISHED IN SUCH A WAY THAT NO DIRECT LIGHT IS CAST UPON OR ADVERSELY AFFECTS ADJACENT PROPERTIES AND ROADWAYS.
  2. LIGHT FIXTURES SHALL INCLUDE GLARE SHIELDS TO LIMIT DIRECT RAYS ONTO ADJACENT RESIDENTIAL PROPERTIES.
  3. ALL LIGHTING FIXTURES (LUMINARIES) SHALL BE CUTOFF LUMINARIES WHOSE SOURCE IS COMPLETELY CONCEALED WITH AN OPAQUE HOUSING. FIXTURES SHALL BE RECESSED IN THE OPAQUE HOUSING. DROP DISH REFRACTORS ARE PROHIBITED.
  4. LIGHT SOURCE SHALL BE LIGHT EMITTING DIODES (LED), METAL HALIDE, OR COLOR CORRECTED HIGH-PRESSURE SODIUM NOT EXCEEDING AN AVERAGE OF FOUR AND ONE-HALF (4.5) FOOT CANDLES OF LIGHT OUTPUT THROUGHOUT THE PARKING AREA. A SINGLE LIGHT SOURCE TYPE SHALL BE USED FOR ANY ONE (1) SITE. FIXTURES MUST BE MOUNTED IN SUCH A MANNER THAT THE CONE OF THE LIGHT IS NOT DIRECTED AT ANY PROPERTY LINE OF SITE.
  5. THE MINIMUM MOUNTING HEIGHT FOR A POLE IS TWELVE (12) FEET. THE MAXIMUM MOUNTING HEIGHT FOR A POLE IS TWENTY-FIVE (25) FEET EXCLUDING A THREE-FOOT BASE.

**DEKALB COUNTY REQUIRED LIGHTING LEVELS:**

Location or Type of Lighting	Minimum Level	Average Level	Maximum Level
Non-residential parking lots	0.6	2.40	18.0
Multifamily residential parking lots	0.2	1.50	10.0
Walkways, access drives and landscaping areas	0.2	2.00	18.0
Landscaped areas	0.0	0.50	3.0



NO.	DATE:	DESCRIPTION	REVISIONS
4			
3			
2			
1			




**LIGHTING PLAN**

PROJECT NAME: **MODWASH**  
1849 LAWRENCEVILLE HWY, DECATUR, GEORGIA


CLIENT: **HUTTON**  
738 CHERRY STREET, CHATTANOOGA, TENNESSEE 37402

PROJECT NO.:	PROJ. MGR.:
DATE:	DRWN. BY:
SCALE:	CHKD. BY:
DRAWING SERIES:	
SHEET NO.:	

DATE: \_\_\_\_\_



C-5.0



DEKALB COUNTY

ITEM NO.

BOARD OF COMMISSIONERS

ZONING AGENDA / MINUTES

MEETING DATE: June 27, 2006

ACTION TYPE

ORDINANCE

HEARING TYPE  
PUBLIC HEARING

SUBJECT: **Rezone** – Chung C. Chang

COMMISSION DISTRICTS: 4 & 6

DEPARTMENT: Planning

PUBLIC HEARING:  YES  NO

ATTACHMENT:  YES  No

INFORMATION CONTACT: Patrick Ejike/Kevin Hunter

PAGES: 19

PHONE NUMBER: (404) 371-2155

Deferred from 5/23/06 for a public hearing.

**PURPOSE:**

**Z-06-1241**

Application of Chung C. Chang to rezone property from M to C-1. The property is located on the southeast corner of Lawrenceville Highway and Jordan Lane. The property has approximately 178 feet of frontage on Lawrenceville Highway and approximately 260 feet of frontage on Jordan Lane and contains 1.27 acres.

**Subject Property:** 18-063

**RECOMMENDATION(S):**

**PLANNING DEPARTMENT:**

APPROVAL. Based on the submitted information as well as field investigation of the project site, it appears that the proposed zoning amendment meets the minimum requirements of the zoning ordinance for approval of the zoning proposal. It should be noted that the submitted site plan depicts building setbacks that do not meet building requirements of the zoning ordinance. Therefore, approval cannot be conditioned on the submitted site plan. In any event, it is the recommendation of the Planning and Development Department that this application be "Approved".

**PLANNING COMMISSION:**

Denial.

**COMMUNITY COUNCIL:**


Other (No Quorum)

**FOR USE BY COMMISSION OFFICE/CLERK ONLY**


**ACTION: H21**

MOTION was made by Commissioner Gannon, seconded by Commissioner Ellis, and passed 5-0-0-1, to approve with conditions and site plan submitted by Commissioner Gannon for the record, the rezoning application of Chung C. Chang. Commissioner Johnson was out of the room and not voting.

ADOPTED: JUN 27 2006  
(DATE)


  
PRESIDING OFFICER  
DEKALB COUNTY BOARD OF COMMISSIONERS

CERTIFIED: JUN 27 2006  
(DATE)

  
CLERK,  
DEKALB COUNTY BOARD  
OF COMMISSIONERS

**FOR USE BY CHIEF EXECUTIVE OFFICER ONLY**

APPROVED: JUL 05 2006

  
CHIEF EXECUTIVE OFFICER  
DEKALB COUNTY

VETOED: \_\_\_\_\_

CHIEF EXECUTIVE OFFICER  
DEKALB COUNTY

VETO STATEMENT ATTACHED: \_\_\_\_\_

**MINUTES:**

Charles Chang, 11020 Black Brook Drive, Duluth, Ga. 30097 and Wanda Moore, 23 Hampton Street, McDonough, Ga. 30252, spoke in support of the application.

No one spoke in opposition of the application.

	FOR	AGAINST	ABSTAIN	ABSENT
DISTRICT 1 - ELAINE BOYER	<u>X</u>	_____	_____	_____
DISTRICT 2 - GALE WALLDORFF	<u>X</u>	_____	_____	_____
DISTRICT 3 - LARRY JOHNSON	_____	_____	_____	<u>X</u>
DISTRICT 4 - BURRELL ELLIS	<u>X</u>	_____	_____	_____
DISTRICT 6 - KATHIE GANNON	<u>X</u>	_____	_____	_____
DISTRICT 7 - CONNIE STOKES	<u>X</u>	_____	_____	_____

Z-06-1241  
Chang/Ali

~~11/17~~

M → C1

District 4 - 6

To: MR. Chang

Approve with conditions:

COMM.	
ITEM NO. #21	6/27/06
CLERK'S OFFICE	Chris Jaramal

- the the*
1. Conditioned to office and retail uses only.
  2. No drive-thru restaurants or liquor/package stores.
  3. Building to be set back in line with adjacent property
  4. Parking lot to include as many trees as code allows.
  5. Use existing curb cut on Lawrenceville Highway for ingress and egress and close access on Jordan Lane.


5/23/06

Public hearing start about 10AM - 10:30 and you are item #21

MR Chang

These are the conditions proposed for Mr Ali's rezoning from M to C-1 on the morning of June 27\*. Please let me know if questions

Commissioner GANNON  
404-391-4909




**BEFORE** (c) Copyright 2003, Pictometry International

Z-06-1241

LAWRENCEVILLE HWY

U.S. HWY'S 29&78 GA S.R.8




SITE PLAN

1'-0"=20'-0"

TOTAL PARKING - 108 PARKINGS

<b>C1</b> <small>REVISED</small>	<b>SITE PLAN</b>	<b>ALI BUILDING</b>	 <b>CUSTOM DESIGN &amp; DEVELOPMENT CORPORATION</b> <small>5100 CHEROKEE DRIVE CORNER</small> <small>SUITE 200</small> <small>ATLANTA, GA. 30340</small> <small>TEL: (770)-524-9900 FAX: (770)-524-9930</small>	<small>DATE</small> <small>BY</small> <small>CHKD BY</small> <small>APP'D BY</small>
	<small>NO. OF SHEETS</small> <small>TOTAL SHEETS</small>	<small>NO. OF SHEETS</small> <small>TOTAL SHEETS</small>		<small>NO. OF SHEETS</small> <small>TOTAL SHEETS</small>





--- 42'-6"  
 --- 32'-6"  
 --- 23'-0"  
 --- 16'-0"  
 --- 13'-6"  
 --- G.F.

ELEVATION  
1/4" = 1'-0"

REVISION	BY	DATE
CUSTOM DESIGN & DEVELOPMENT CORPORATION 1000 UNIVERSITY AVENUE, SUITE 100 ANN ARBOR, MI 48106 TEL: (313) 761-1000 FAX: (313) 761-1001		
		
ALL BUILDING		
ELEVATION		
DRAWN BY		
SCALE AS SHOWN		
PROJECT NO.		
DATE PLOTTED		
A1		

DEPARTMENT OF PLANNING & SUSTAINABILITY

DISCLOSURE OF CAMPAIGN CONTRIBUTION

In accordance with the Conflict of Interest in Zoning Act, OCGA Chapter 36-67A, the following questions must be answered.

Have you, the applicant, made \$250.00 or more in campaign contribution to a local government official within two years immediately preceding the filling of this application?

Yes \_\_\_\_\_ No X \*

If the answer is yes, you must file a disclosure report with the governing authority of DeKalb County showing:

1. The name and official position of the local government official to whom the campaign contribution was made.
2. The dollar amount and description of each campaign contribution made during the two years immediately preceding the filing of this application and the date of each such contribution.


The disclosure must be filed within 10 days after the application is first filed and must be submitted to the C.E.O. and to the Board of Commissioners of DeKalb County, 1300 Commerce Drive, Decatur, GA 30030.

[Signature]  
Notary

ModWash, LLC  
By: [Signature]  
Signature of Applicant /Date

Check one: Owner \_\_\_\_\_ Agent X

12/10/2025  
Expiration Date/ Seal



\*Notary seal not needed if answer is "no".

**DEPARTMENT OF PLANNING & SUSTAINABILITY**

**DISCLOSURE OF CAMPAIGN CONTRIBUTION**

In accordance with the Conflict of Interest in Zoning Act, OCGA Chapter 36-67A, the following questions must be answered.


Have you, the applicant, made \$250.00 or more in campaign contribution to a local government official within two years immediately preceding the filing of this application?

Yes \_\_\_\_\_ No  \*

If the answer is yes, you must file a disclosure report with the governing authority of DeKalb County showing:

1. The name and official position of the local government official to whom the campaign contribution was made.
2. The dollar amount and description of each campaign contribution made during the two years immediately preceding the filing of this application and the date of each such contribution.

The disclosure must be filed within 10 days after the application is first filed and must be submitted to the C.E.O. and to the Board of Commissioners of DeKalb County, 1300 Commerce Drive, Decatur, GA 30030.

  
\_\_\_\_\_  
Notary



06/10/2023  
Expiration Date/ Seal

6/7/22

Karimshah Inc

By: 

Signature of Applicant /Date

Check one: Owner  Agent \_\_\_\_\_

\*Notary seal not needed if answer is "no".

DEPARTMENT OF PLANNING & SUSTAINABILITY

DISCLOSURE OF CAMPAIGN CONTRIBUTION

In accordance with the Conflict of Interest in Zoning Act, OCGA Chapter 36-67A, the following questions must be answered.

Have you, the applicant, made \$250.00 or more in campaign contribution to a local government official within two years immediately preceding the filing of this application?

Yes  No  \*


If the answer is yes, you must file a disclosure report with the governing authority of DeKalb County showing:

1. The name and official position of the local government official to whom the campaign contribution was made.
2. The dollar amount and description of each campaign contribution made during the two years immediately preceding the filing of this application and the date of each such contribution.

The disclosure must be filed within 10 days after the application is first filed and must be submitted to the C.E.O. and to the Board of Commissioners of DeKalb County, 1300 Commerce Drive, Decatur, GA 30030.

  
Notary



  
Signature of Applicant /Date

Check one: Owner  Agent

08/18/25  
Expiration Date/ Seal

\*Notary seal not needed if answer is "no".

Campaign Contribution Disclosure Statements  
Last Updated 6/17/2022

**CAMPAIGN CONTRIBUTIONS DISCLOSURE STATEMENT**


Pursuant to the provisions of 36 O.C.G.A. 67(A), please find below a list of those contributions made by Michèle L Battle or Battle Law, P.C. in the past two years, aggregating \$250.00 or more, to local government officials who will consider this application.

<b>NAME OF GOV'T OFFICIAL</b>	<b>OFFICIAL POSITION</b>	<b>AMOUNT OF CONTRIBUTION</b>
Ted Terry	<b>Commissioner</b>	<b>\$500</b>
Mereda Davis Johnson	<b>Commissioner</b>	<b>\$250</b>
Lorraine Cochran-Johnson	<b>Commissioner</b>	<b>\$750</b>


By:   
Printed Name: Michele L. Battle

# ModWash CarWash

# PINE TOWNSHIP WEXFORD, PA




8" x 4" x 16" CMU  
INTERGRAL COLORED  
SNOW RANGE




8" x 4" x 16" CMU  
INTERGRAL COLORED  
OYSTER RANGE




METAL ROOFING  
PREWEATHERED  
GALVALUME



EXIT ELEVATION



ENTRY ELEVATION



TUNNEL ELEVATION



VACUUM ELEVATION



# Battle Law

## STATEMENT OF INTENT

and

Other Material Required by  
DeKalb County Zoning Ordinance  
For  
A Special Land Use Permit for a  
Drive-Thru Facility

of

**MODWASH, LLC.**  
**c/o Battle Law, P.C.**

for

**+/-1.26 Acres of Land**  
Being 1849 Lawrenceville Highway  
DeKalb County, Georgia and  
Parcel Nos. 18 063 03 027

Submitted for Applicant by:

Michèle L. Battle, Esq.  
Battle Law, P.C.  
Habersham at Northlake, Building J, Suite 100  
Tucker, Georgia 300384  
(404) 601-7616 Phone  
(404) 745-0045 Facsimile  
[mlb@battlelawpc.com](mailto:mlb@battlelawpc.com)



# Battle Law

## **I. LETTER OF INTENT**

ModWash, LLC. (the “Applicant”) is seeking to develop on +/- 1.26 of land being Tax Parcel No. 18 063 03 027 having frontage on 1849 Lawrenceville Highway (the “Subject Property”) with a luxury drive-thru car wash facility. The Applicant is seeking a Special Land Use Permit for the Subject Property to allow for the Drive-Thru Facility.

This document serves as a statement of intent, analysis of the criteria under the DeKalb County Zoning Ordinance and contains notice of constitutional allegations as a reservation of the Applicant’s rights.

## **II. SPECIAL LAND USE PERMIT CRITERIA**

*A. Adequacy of the size of the site for use contemplated and whether or not adequate land area is available for the proposed use including provision of all required yards, open space, off-street parking, transitional buffer zones, and all other applicable requirements of the zoning district in which the use is proposed to be located.*

The size of the site is adequate for the contemplated use and for the inclusion of all required yards, open space, off-street parking, and all other applicable requirements of the zoning district in which the use is proposed to be located. The site plan submitted with this application satisfies all zoning requirements under the existing C-1 zoning district and comfortably fits the proposed drive-thru car wash along with the required off-street parking, landscape strips and plantings. Therefore, the size of the site is adequate for the contemplated use.

*B. Compatibility of the proposed use with adjacent properties and land use and other properties and land uses in the district, and whether the proposed use will create adverse impacts upon any adjoining land use by reason of traffic volume/congestion, noise, smoke, odor, dust, or vibration generated by the proposed use.*

The zoning proposal will permit a use that is suitable in view of the use and development of adjacent and nearby properties. The Subject Property is immediately abutted by properties zoned for commercial and industrial uses. So, the nearest neighbors to the Subject Property will be used for similar uses. Across Jordan Lane, there are some residential uses. The community members have indicated that luxury express car wash may be a use they can support so long as there is a suitable lighting package that does not shine light across the street onto their homes, that the ingress/egress onto Jordan Lane be closed, and that the operation wraps up at a reasonable hour so as not to disturb them late into the evening. The Applicant has agreed to these stipulations and has agreed to plant trees between the proposed car wash and the residential uses in the landscape strip. The trees would serve to screen the use from the residential use. Therefore, the zoning proposal will permit a use that is suitable in view of the adjacent and nearby properties.

The proposed use will not create adverse impacts upon any adjoining land use by reason of noise, smoke, odor, dust, or vibration generated by the proposed use.





## Battle Law

*C. Adequacy of public services, public or private facilities, public or private streets (including consideration of traffic- carrying capacity), and utilities to serve the use contemplated.*

The zoning proposal will not result in a use which will or could cause excessive or burdensome use of existing streets, transportation facilities, utilities, or schools. With proper conditions that limit the use to the proposed car wash, there will be no need to worry about any other commercial uses coming to this site. Any change in the use would require a Major Modification and public hearing process like the one the Applicant is currently applying for. This would allow the County and community members oversight in determining whether any other use is welcome on the Subject Property.

Additionally, the proposed use will not cause excessive use of existing streets, transportation facilities, utilities, or schools. The Subject Property fronts on Lawrenceville Highway, which is classified as a Major Arterial street. It is certainly capable of handling any trips generated by this use. Additionally, there will be no impact on schools or transportation facilities. Lastly, the Applicant uses technology to capture as much used water as possible for reuse in washing vehicles. The goal is to use as little water as possible while operating the car wash. This minimizes the impact on water utilities. Therefore, the zoning proposal will not result in a use which will or could cause excessive or burdensome use of existing streets, transportation facilities, utilities, or schools.

*D. Adequacy of the public street on which the use is proposed to be located and whether there is sufficient traffic carrying capacity for the use proposed so as not to unduly increase traffic and create congestion in the area.*

The public street on which this use is proposed to be located is adequate to support the proposed use. Lawrenceville Highway is a Major Arterial Street, capable of carrying large amounts of traffic. The proposed car wash will not overwhelm traffic on Lawrenceville Highway

Additionally, the proposed use includes closing the currently open driveway that fronts on Jordan Lane. This will prevent traffic cutting through the proposed use and exiting onto Jordan Lane. The Community made very clear that this must be a part of the development, and the Applicant has obliged. Therefore, the public street on which this use is proposed to be located is adequate to support the proposed use.

*E. Adequacy of ingress and egress to the subject property and to all proposed buildings, structures and uses thereon with particular reference to pedestrian and automotive safety and convenience, traffic flow and control and access in the event of fire or other emergency.*

There is adequate ingress and egress to the Subject Property and to all proposed buildings, structures, and uses thereon. The proposed use shows an ingress/egress point off of Lawrenceville Highway and proposes closing the access on Jordan Lane. The Subject Property was once the subject of a prior zoning case which placed a condition on the rezoning of the



## Battle Law

Subject Property that instructed the owner to close the access onto Jordan Lane. This was never done, and the Community has made clear that they want the access onto Jordan Lane closed. The Applicant can maintain adequate ingress/egress onto the Subject Property via Lawrenceville Highway while still accommodating the wishes of the Community. Therefore, there is adequate ingress and egress to the Subject Property and to all proposed buildings, structures, and uses thereon.

*F. Whether the proposed use will create adverse impacts upon any adjoining land use by reason of the manner and hours of operation of the proposed use.*

The proposed use will not create adverse impacts upon any adjoining land use by reason of the hours of operation of the proposed use. While meeting with the Community, the Applicant heard concerns about the hours of operation and how they might affect the residential uses across Jordan Lane. The Applicant expressed to the Community that the proposed use would be. There are no other adjoining land uses that would be affected by the proposed use due to hours of operation. Therefore, the proposed use will not create adverse impacts upon any adjoining land use by reason of the hours of operation of the proposed use.

*G. Whether the proposed use is otherwise consistent with the requirements of the zoning district classification in which the use is proposed to be located.*

The proposed use is otherwise consistent with the requirements of the zoning district classification in which the use is proposed to be located.

*H. Whether the proposed use is consistent with the policies of the comprehensive plan.*

The proposed use is consistent with the policies of the comprehensive plan.

*I. Whether there is adequate provision of refuse and service areas.*

There is adequate provision of refuse and service areas.

*J. Whether the length of time for which the special land use permit is granted should be limited in duration.*

The length of time for which the Special Land Use Permit is granted should not be limited in duration. Limiting the time for which the special land use permit is granted would limit the duration of time the proposed business could operate legally. A time limit placed on a Special Land Use Permit that permits a business that intends to operate in the future indefinitely only creates the opportunity for the future business to become a non-conforming use. Therefore, the length of time for which the Special Land Use Permit is granted should not be limited in duration.



## Battle Law

*K. Whether the size, scale and massing of proposed buildings are appropriate in relation to the size of the subject property and in relation to the size, scale and massing of the adjacent and nearby lots and buildings, and whether the proposed use will create a shadow impact on any adjoining lot or building, as a result of the proposed building height.*

The size, scale, and massing of proposed buildings are appropriate in relation to the size of the Subject Property and in relation to the size, scale, and massing of adjacent and nearby lots and buildings. The only proposed building on the Subject Property is the proposed luxury drive-thru car wash facility. Vacuum structures will also be a part of the proposed development, but there is plenty of space to allow for the building and vacuum structures. Therefore, the size, scale, and massing of proposed buildings are appropriate in relation to the size of the subject property and in relation to the size of the subject Property and in relation to the size, scale, and massing of adjacent and nearby lots and buildings.

*L. Whether the proposed plan will adversely affect historic buildings, sites, districts, or archaeological resources.*

The proposed use will not adversely affect historic buildings, sites, districts, or archaeological resources. The Subject Property is not located in a historic district, nor on a historic site and is currently vacant, so has no historic buildings on it. There are no historic buildings nearby either. Therefore, the proposed use will not adversely affect historic buildings, sites, districts, or archaeological resources.

*M. Whether the proposed use satisfies the requirements contained within the Supplemental Regulations for such special land use permit.*

The proposed use satisfies the requirements contained within the supplemental regulations for the applied-for Special Land Use Permit.

*N. Whether the proposed use would be consistent with the needs of the neighborhood or the community as a whole, be compatible with the neighborhood, and would not be in conflict with the overall objectives of the comprehensive plan.*

The proposed use will be consistent with the needs of the neighborhood or community as a whole, be compatible with the neighborhood, and would not be in conflict with the overall objective of the comprehensive plan. The Applicant does not propose to amend the comprehensive land use plan or rezone the Subject Property. Rather, the Applicant only needs to change a condition on the Subject Property as a result of a prior rezoning case (application submitted separately) and apply for this Special Land Use Permit. Thus, the proposed use is in line with the plan for this property. Therefore, the proposed use will be consistent with the needs of the neighborhood or community as a whole, be compatible with the neighborhood, and would not be in conflict with the overall objective of the comprehensive plan.

### **III. CONCLUSION**



## Battle Law

For the foregoing reasons, the Applicant hereby requests that the application for a Special Land Use Permit to allow for a Drive-Thru Facility be approved. The Applicant welcomes any questions and feedback from the planning staff.

### **IV. NOTICE OF CONSTITUTIONAL ALLEGATIONS AND PRESERVATION OF CONSTITUTIONAL RIGHTS**

The portions of the DeKalb County Zoning Ordinance, facially and as applied to the Subject Property, which restrict or classify or may restrict or classify the Subject Property so as to prohibit its development as proposed by the Applicant are or would be unconstitutional in that they would destroy the Applicant's property rights without first paying fair, adequate and just compensation for such rights, in violation of the Fifth Amendment and Fourteenth Amendment of the Constitution of the United States and Article I, Section I, Paragraph I of the Constitution of the State of Georgia of 1983, Article I, Section III, Paragraph I of the Constitution of the State of Georgia of 1983, and would be in violation of the Commerce Clause, Article I, Section 8, Clause 3 of the Constitution of the United States.

The application of the DeKalb County Zoning Ordinance to the Subject Property which restricts its use to any classification other than that proposed by the Applicant is unconstitutional, illegal, null and void, constituting a taking of Applicant's Property in violation of the Just Compensation Clause of the Fifth Amendment to the Constitution of the United States, Article I, Section I, Paragraph I, and Article I, Section III, Paragraph I of the Constitution of the State of Georgia of 1983, and the Equal Protection and Due Process Clauses of the Fourteenth Amendment to the Constitution of the United States denying the Applicant an economically viable use of its land while not substantially advancing legitimate state interests.

A denial of this Application would constitute an arbitrary irrational abuse of discretion and unreasonable use of the zoning power because they bear no substantial relationship to the public health, safety, morality or general welfare of the public and substantially harm the Applicant in violation of the due process and equal protection rights guaranteed by the Fifth Amendment and Fourteenth Amendment of the Constitution of the United States, and Article I, Section I, Paragraph I and Article I, Section III, Paragraph 1 of the Constitution of the State of Georgia.

A refusal by the DeKalb County Board of Commissioners to amend the land use and/or rezone the Subject Property to the classification as requested by the Applicant, or to grant the requested Special Land Use Permit, would be unconstitutional and discriminate in an arbitrary, capricious and unreasonable manner between the Applicant and owners of similarly situated property in violation of Article I, Section I, Paragraph II of the Constitution of the State of Georgia of 1983 and the Equal Protection Clause of the Fourteenth Amendment to the Constitution of the United States. Any Special Land Use Permit applied to the Property subject to conditions which are different from the conditions requested by the Applicant, to the extent such different conditions would have the effect of further restricting Applicant's utilization of the property, would also constitute an arbitrary, capricious and discriminatory act in zoning the Subject Property to an unconstitutional classification and would likewise violate each of the provisions of the State and Federal Constitutions set forth hereinabove.



## Battle Law

A refusal to allow the land use amendment and/or Special Land Use Permit in questions would be unjustified from a fact-based standpoint and instead would result only from constituent opposition, which would be an unlawful delegation of authority in violation of Article IX, Section II, Paragraph IV of the Georgia Constitution.

A refusal to allow the land use amendment and/or Special Land Use Permit in question would be invalid inasmuch as it would be denied pursuant to an ordinance which is not in compliance with the Zoning Procedures Law, O.C.G.A Section 36-66/1 et seq., due to the manner in which the Ordinance as a whole and its map(s) have been adopted.

The existing land use designation and/or zoning classification on the Subject Property is unconstitutional as it applies to the Subject Property. This notice is being given to comply with the provisions of O.C.G.A. Section 36-11-1 to afford the County an opportunity to revise the Property to a constitutional classification. If action is not taken by the County to rectify this unconstitutional land use designation and/or zoning classification within a reasonable time, the Applicant is hereby placing the County on notice that it may elect to file a claim in the Superior Court of Fulton County demanding just and adequate compensation under Georgia law for the taking of the Subject Property, diminution of value of the Subject Property, attorney's fees and other damages arising out of the unlawful deprivation of the Applicant's property rights.

---

Michele L. Battle, Esq.  
Attorney for the Applicant



May 4, 2022

Site: ModWash  
Wash Info: NCS (Tunnel)  
Subject: Water Usage Information  
To Whom It May Concern:

The PurWater Recovery System has been engineered and designed specifically with the Professional Car Wash Operator in mind and incorporates the same innovative, cutting edge technology the industry has come to expect from PurClean. Modular in design, the PurWater System platform provides a simplified approach that allows the system to be easily adapted to meet the needs and requirements of the targeted wash facility and eliminates the confusion typically associated with water recovery.

**NCS– Tunnel**

It is a commonly used number that you will lose 6 gallons to evaporation and carry out. Using 38.9 gallons total (reclaim, RO, RO reject and freshwater) per vehicle will put you at 75.99% reclaim which should be a good balance of wash quality and conservation. With your chemical applications and final rinse applications at 13.9 gallons per vehicle, all your undercarriage, and all cloth applications running on reclaimed water you will be at 7.9 gallons per vehicle going to sewer.

**Water Use Per Vehicle**

- ◆ evaporation and carry out 6 gallons
- ◆ chemical application and final rinse (RO, RO reject and freshwater) 13.9 gallons
- ◆ undercarriage and wash applications running on reclaim water 25 gallons
- ◆ at maximum going to sewer 7.9 gallons of reclaim water

**Summary**

- ◆ Total of 38.9 gallons of water used per vehicle
- ◆ 13.9 gallons of RO, RO reject and freshwater for chemistry
- ◆ 25 gallons of water for the wash / recycle
- ◆ 6 gallons of water lost to evaporation and carry out
- ◆ 7.9 gallons going to the sewer – calculates to 80.28% reclaim

**Total Gallons to Sewer Daily (estimated at 500 cars per day count)**

- ◆ 7.9 gallons per vehicle going to sewer (estimated 1000 cars per day) total to sewer per day 3,950 gallons

**Total Gallons Freshwater, RO & Reject used (estimated at 500 cars per day count)**

- ◆ 13.9 gallons per vehicle which includes freshwater, RO & RO Reject (estimated 1000 cars per day) total freshwater used per day is 6,950 gallons

Best Regards,


*Steven Samudio*

Steven Samudio  
Technical Sales Manager  
PurClean

Mod Wash

Application	Gallons Used	Fresh/Reclaim
FOAMING APPLICATOR ARCH	1.5	Fresh
FOAMY CTA #1	0.3	Fresh
FOAMY CTA #2	0.3	Fresh
TOTAL BATH	0.6	Fresh
WRAP FOAMER #1	1	Fresh
WRAP AROUND WATER #1	4	Reclaim
TRIPLE POLISH	0.45	Fresh
MITTER #1	1.33	Reclaim
WRAP FOAMER #2	1	Fresh
WRAP AROUND WATER #2	4	Reclaim
TOTAL SHINE	0.2	Fresh
SFB21	1.33	Reclaim
UNDERCARRIAGE	1	Reclaim
OMNI TOP	6.67	Reclaim
OMNI SIDES	6.67	Reclaim
HOT WAX	0.9	Fresh
807 MITTER	1.33	Fresh
SFB28	1.33	Fresh
WATERFALL	0.53	Fresh
TOTAL SEAL	0.6	Fresh
LP MIRROR RINSE	1	Fresh
DRYING AGENT	1.33	Fresh
SEALER WAX	0.2	Fresh
FINAL RINSE	1.33	Fresh

	Total	38.9
Evaporation and Drive Off Gallons		-6.0
Fresh Water Usage Gallons		13.90
Reclaim Water Usage Gallons		25.0
Reclaim Percentage		75.99%
Fresh Water Percentage		35.73%
Evaporation and Drive off Percentage		-11.72%
		100.00%





June 18, 2018

**Reclaim Effluent Quality Estimate for  
PurWater Reclaim Systems**

Vehicles will attract contaminants predicated on the region of the country, and the roads traveled. These contaminants will consist of soil, road film, tree sap, bird droppings, pollen, insects, oil, and greases. Depending on if the region has snow and ice, then whatever will stick in the snow and ice will also stick to the vehicle. Snow and ice removal materials, which include but are not limited to sand, salt, liquid magnesium chloride which is often applied with a molasses to help it adhere to the road can and will stick to your vehicle as well. All of these contaminants will wash from the vehicle and will end up in the water reclamation tanking system.

The PurWater Reclaim System consists of two primary components ... the underground reclaim tank(s) and the above ground PurWater unit. The below ground tanks are normally supplied by a local concrete vault vendor, with their capacity and lay-out per PurWater specifications. The primary purpose of the reclaim system is to provide quality water to the wash so that the water can be re-used within the wash and still provide a clean car. The re-use of the water allows the operator to minimize the amount of incoming fresh water to the wash and the amount that is discharged from the wash. The reclaim system is not designed to meet a specific effluent quality of the discharge, although in many cases the water discharged from the system goes directly to sewer or a leach field.

As the primary purpose of the PurWater Reclaim System is to provide quality water for re-use within the wash, the system is designed to separate settleable solids (typically sand, grit) and free oils from the water going to the wash. These solids and oils can affect the wash quality, and increase the maintenance on wash pumps, piping, and nozzles. The large settleable solids (60-70 micron and larger) are settled within the underground tanks prior to entering the above ground PurWater unit. The PurWater unit uses high efficiency cyclones to remove down to 5 micron settleable solids prior to the wash. The solids-laden water from the PurWater unit is re-introduced into the reclaim water at the front end of the underground tanks, where some solids settle and some continue with the water phase to be re-treated or go out with the effluent. The free oils (60-70 micron and larger) float to the surface within the underground tanks and are trapped within the tanks. Accumulated settleable solids and free oils are periodically (normally every 3-6 months) removed from the reclaim system by pumping out the underground tanks and replacing with fresh water.

Some amount of water is continuously discharged from the reclaim system in order to satisfy the water balance for the wash. The volume of discharge is dependent on the amount of fresh water used by the wash, less any water that is lost to evaporation and carry-out. Depending upon local municipal requirements, the discharge can be sent directly to sewer or to a leach field, or may require additional treatment before final discharge. As each municipality will have its own discharge requirements, it is important to understand what contaminants the PurWater Reclaim System can and cannot affect.

The PurWater Reclaim system uses two processes to reduce contaminant loading. The first is physical separation using centrifugal force (the cyclones) and gravity settling (the reclaim tanks). Physical separation will directly affect the amount of free oil & grease (FOG) and total suspended solids (TSS) left in the discharge water, and indirectly affect the BOD / COD level as it removes oil & grease. The second process is chemical, oxidation using ozone. Ozone will affect the bacterial count, BOD / COD, total suspended solids (primarily bacterial), and some dissolved oils and chemicals. From field testing and experience, the PurWater Reclaim system has been shown to produce effluent qualities as follows:

CONTINUED NEX PAGE



Total Suspended Solids (TSS): 15-100 ppm  
Free Oil & Grease (FOG): 10-25 ppm  
BOD: 15-50 ppm

TSS, FOG, and BOD are typically the main concerns by municipalities receiving an effluent from a car wash. Given the type of processes used by the PurWater Reclaim system, there is no effect on total dissolved solids (TDS), pH, or temperature. There may also be little to no effect on certain chemicals dissolved in the water, emulsified or dissolved oils, and non-settleable solids.

The above effluent qualities are going to be similar for other types of systems that incorporate physical separation (plate separators, screen / bag filters, media filters, etc.) and chemical oxidation. Biological processes, when operating properly, may produce lower TSS, FOG, and BOD levels than the above, but still will not affect dissolved minerals and some dissolved chemicals in the water.

The above effluent quality estimates are based on normal contaminant loadings seen by car washes. The estimates are not a guarantee of performance. The estimated discharge quality from the PurWater Reclaim System may or may not be acceptable for direct discharge to sewer or a leach field. Local authorities and municipalities should be consulted to determine whether additional treatment is required to meet discharge permits.

If you have any questions or comments on the above, please contact our Sacramento office.

Sincerely,

*Teresa Borchard*

Teresa Borchard  
Director of Technical Sales and Project Management  
New Wave Industries  
PurClean / PurWater



**PurWater Reclaim System Design**

The PurWater Reclaim System consists of two primary components the underground reclaim tank(s) and the above ground PurWater unit. The below ground tanks are normally supplied by a local concrete vault vendor, with their capacity and lay-out per PurWater specifications. (See attached drawing.) The primary purpose of the reclaim system is to provide quality water to the wash so that the water can be re-used within the wash and still provide a clean car. The re-use of the water allows the operator to minimize the amount of incoming fresh water to the wash and the amount that is discharged from the wash. The reclaim system is not designed to meet a specific effluent quality of the discharge, although in many cases the water discharged from the system goes directly to sewer or a leach field.

As the primary purpose of the PurWater Reclaim System is to provide quality water for re-use within the wash, the system is designed to separate settleable solids (typically sand, grit) and free hydrocarbons, from fat oil and greases, from the water going to the wash. These solids and hydrocarbons can affect the wash quality, and increase the maintenance on wash pumps, piping, and nozzles. The large settleable solids are settled within the underground tanks prior to entering the above ground PurWater unit. The free hydrocarbons float to the surface within the underground tanks and are trapped within the tanks. Accumulated settleable solids and free hydrocarbons are periodically (normally every 6-12 months) removed from the reclaim system by pumping out the underground tanks and replacing with fresh water. **This is a recommendation only; local regulations may require more frequent service.**

There are two factors we use in determining the size of the reclaim tanks for use with our PurWater Reclaim Units. The first consideration is the size of solid particle we want to separate within the reclaim tanks and the second consideration is how often we treat the water in the tanks using the continuous recirculation. The following will provide details on both of these factors:

- 1) Particle Removal: In the reclaim tank system, we are typically looking to remove solid particles between 60 – 75 microns in size. This ensures large particles are not going through the PurWater unit, which can cause excessive wear and / or plugging. Also, the size of the tanks needed for this removal allows for a relatively large volume for a sludge layer to build so that tanks do not need frequent clean-out. Particle size removal is determined by Stoke’s Law:

$$V (R/S) = (g \times (\text{Rho1} - \text{Rho2}) \times D^2) / 18 \text{ Nu}$$

Where:

V (R/S) = Rise or Settling Velocity of a Particle (cm / sec)

g = Acceleration by Gravity (cm / sec<sup>2</sup>)

Rho1 = Density of Medium (g / cm<sup>3</sup>)

Rho2 = Density of Particle (g / cm<sup>3</sup>)

D = Particle Diameter (cm)

Nu = Viscosity of Medium (g / cm / sec)

We assume a water temperature of 68 DegF, which provides a water density of 1.0 g / cm<sup>3</sup> and a viscosity of 1 cp (0.01 g / cm / sec). The solids density we use is 1.2 g / cm<sup>3</sup>, which is typically the lighter solids (silt) found in car washes. The acceleration of gravity is 980 cm / sec<sup>2</sup>.

For a 60 micron (0.006 cm) particle, the settling velocity is 0.039 cm / sec, or 0.93 in / min. For a 75 micron (0.0075 cm) particle, the settling velocity is 0.061 cm / sec, or 1.45 in / min. We now use these velocities to determine the tank volume.

CONTINUED NEXT PAGE

We typically recommend using a tank that is 11 ft long (I.D.) by 5 ft wide (I.D.) with a 4.5 ft water depth. We allow for 1 foot at the bottom to be sludge accumulation, so we assume a solids particle must travel a maximum of 3.5 feet (42 in) to be removed. This leaves us with approximately 1440 gallons per tank of working volume (excluding the sludge layer).

For example, we will assume the maximum flow to the reclaim unit is 90 gpm (our PW300 series). To remove 60 micron particles, it will take a working tank volume of 4065 gallons (90 gpm x 42 in travel distance / 0.93 in per minute settling velocity), or 2.8 tanks (4065 gallons / 1440 gallons per tank of working volume). To remove 75 micron particles, it will take a working tank volume of 2606 gallons, or 1.8 tanks. We typically recommend using three tanks for this flow rate.

- 2) Treatment Frequency: One of the functions of the PurWater system is to continuously recirculate water through the reclaim tanks to provide odor control and to keep the water in the tanks from going stagnant. We recommend treating the entire reclaim tank working volume at least 2-3 times per day. On average, the PurWater unit recirculates water at 12 gpm. Using three tanks (per our example above), the entire working volume will be treated every 6 hours (3 tanks x 1440 gallons per tank / 12 gpm), or 4 times per day. This treatment frequency is well within our guidelines.

Some amount of water is continuously discharged from the reclaim system in order to satisfy the water balance for the wash. The volume of discharge is dependent on the amount of fresh water used by the wash, less any water that is lost to evaporation and carry-out. The discharge is sent to a separate, customer supplied wastewater treatment device, or directly to sewer or a leach field. The PurWater Reclaim System does not treat or affect minerals or chemicals dissolved in the water, emulsified or dissolved oils, non-settleable solids, the BOD / COD content, pH, or temperature of the water that is discharged.

The second component of the reclaim system is the above ground treatment system, which further removes solids from the reclaim water so that it is acceptable for the high pressure pumps and nozzles within the wash. The PurWater reclaim unit has a suction pump that brings water up from the reclaim tank to be treated. The pump speed is controlled by a Variable Frequency Drive (VFD) to either continuously recirculate water (low speed) or to provide water to the wash (high speed). Several pump speeds can be programmed into the VFD to meet various or multiple demands. The PurWater unit uses high efficiency cyclones to remove down to 5 micron settleable solids prior to the wash. The cyclones create nearly 1000 G's of centrifugal force to obtain this fine particle separation. The treated (cleaned) water is sent to the wash and / or back to the reclaim tank as part of its continual recirculation mode. The solids-laden water from the PurWater unit is re-introduced into the reclaim water at the front end of the underground tanks, where some solids settle and some continue with the water phase to be re-treated or go out with the effluent.

The above ground reclaim system also has the function of providing odor control for the reclaim water. Reclaim water is a great environment for growing bacteria which can create plugging and odor problems. Typically, anaerobic bacteria (bacteria that grow in the absence of oxygen) will grow beneath the settled solids in the reclaim water tank. This type of bacteria produces hydrogen sulfide which produces an odor similar to rotten eggs. To control this bacterial growth, the PurWater reclaim system continuously recirculates water through the tanks to keep the water moving so that it does not go septic. The PurWater system also incorporates one of three odor control devices to further keep the bacterial growth in check. The first method uses an Air Sparger, which brings in air as the recirculation water passes through it. This puts oxygen in the water stream and helps control the anaerobic bacteria. The second method adds an enzyme into the recirculation water, plus uses the Air Sparger. The enzyme breaks down the dissolved organic material in the water, which takes away the bacteria's food source to keep their population controlled. The third method used is the addition of ozone, which is a powerful disinfectant similar to chlorine. The ozone kills the bacteria to provide a nearly bacteria free water. Also, ozone oxidizes dyes in the water, so it will remove the color created by wash chemicals (i.e. triple foams).

Attached are spec sheets and drawings of typical underground reclaim tanks and PurWater reclaim systems. If you have any questions or comments on the above, please contact our Sacramento office.

Sincerely,

*Teresa Borchard*

Teresa Borchard  
Director of Technical Sales and Project Management  
New Wave Industries  
PurClean/PurWater