



January 29, 2021

Atlas  
2450 Commerce Ave.  
Suite 100  
Duluth, GA 30096-8910

ATTN: Lloyd Ellison

RE: ITB 19-101072 – Rockbridge Road  
PI # 0008121/0012789  
Lower Sanitary Sewer Laterals in conflict with storm drain  
Revised - Reduced Overhead

Dear Mr. Ellison:

Per your request we are providing a unit cost to lower existing sanitary sewer laterals that are in conflict with the elevations of the proposed storm drain system.

The unit price along with a unit price breakdown is provided below.

<b>CHANGE ORDER REQUEST</b>					
<b>DESCRIPTION</b>	<b>QTY</b>	<b>UNIT</b>	<b>UNIT PRICE</b>	<b>TOTAL</b>	
LOWER SEWER LATERAL	2.000	EA	\$ 13,087.36	\$	26,174.72
 <b>COST BREAKDOWN</b>					
<b>SUBCONTRACTOR COST</b>					
LABOR	7,500.000				
MATERIAL					
# 57 STONE ( 18 TONS INCL HAUL)	\$500.00				
PIPE MATERIAL (6" PVC PIPE, FITTINGS, COUPLINGS)	\$900.00				
SHORING BOX RENTAL	\$1,500.00				
<b>SUB TOTAL</b>	<b>\$10,400.00</b>				
 <b>ERS MARKUP AND OVERHEAD</b>					
OVERHEAD 4%	\$416.00				
PROFIT 10%	\$1,081.60				
BOND 1%	\$1,189.76				
<b>TOTAL UNIT PRICE</b>	<b>\$13,087.36</b>				

ERS and MVP will insist that both DeKalb Watershed and Dekalb Transportation sign off and agree to pay the unit price as specified before we will proceed with this work.

E. R. Snell Contractor, Inc.

[www.ersnell.com](http://www.ersnell.com) | 770.985.0600 | 1785 Oak Road, Snellville, GA 30078



If any field exploration is requested by DeKalb Watershed or DeKalb Transportation over and above what we already intend to determine the exact locations and elevations of the tie in points, this work will be charged separately at the unit rate of \$350.00 per hour.

Kind regards,

A handwritten signature in blue ink, appearing to read 'F.R. Price III', is written over a horizontal line.

F.R. Price III  
Vice President  
E.R. Snell Contractor, Inc.

E. R. Snell Contractor, Inc.

 [www.ersnell.com](http://www.ersnell.com) |  770.985.0600 |  1785 Oak Road, Snellville, GA 30078