Seminole Rd. Landfill Cell Construction Phase 3, Unit 2; Cell 1 Cell 2 Subgrade



Bid Opening: July 12, 2019

Cost Opening: July 19, 2019

Procurement Agent: Jovan Hooper

DEPARTMENT OF PURCHASING & CONTRACTING BID EVALUATION

Item No.	Description	I nif		Mor	gan Corp.	
			Estimated Quantity	Unit Price (\$)	Total Amount (\$)	
	CELL NO	. 1 & CELL 1	NO. 2 SUBGRAD	E		
1	Mobilization/Demobilization	LS	1	\$665,000.00	\$665,000.00	
2	Project Survey - Cell 1 & Cell 2	LS	1	\$200,000.00	\$200,000.00	
3	Site Clearing, Grubbing, and Stripping - Cell 1, Leachate Tank & Cell 2	LS	1	\$150,000.00	\$150,000.00	
4	Erosion and Sediment Control - Cell 1, Leachate Tank & Cell 2	LS	1	\$400,000.00	\$400,000.00	
5	Subgrade, Stormwater Swale, Sediment Pond, and Leachate Tank - Cut - Cell 1 & 2	CY	115,400	\$5.00	\$577,000.00	
6	Waste Removal for Tie-in to Existing Liner - Cut - Cell 1	CY	8,700	\$11.00	\$95,700.00	
7	Subgrade, Embankment, Roads, Stormwater Swale, and Leachate Tank - Fill - Stockpile adjacent to construction area - Cell 1	CY	187,000	\$4.50	\$841,500.00	
8	Stormwater Structures and Piping - Cell 1 & Cell 2	LS	1	\$705,000.00	\$705,000.00	
9	6" Clay Subbase, Imported Soils - Cell 1	CY	8,100	\$125.00	\$1,012,500.00	
10	Geosynthetic Clay Liner - Cell 1	SF	432,682	\$1.00	\$432,682.00	
11	60 mil Textured HDPE Geomembrane Liner, Primary and Secondary, Cell 1	SF	865,363	\$1.09	\$943,245.67	
12	Geocomposite, Primary and Secondary - Cell 1	SF	865,363	\$0.75	\$649,022.25	
13	Protective Layer/Drainage Sand Layer, 24-inches Minimum Thickness, Imported Soils - Cell 1	CY	32,050	\$105.00	\$3,365,250.00	
14	12-mil Geosynthetic Rain Tarp with Sandbags - Cell 1	SF	432,682	\$0.50	\$216,341.00	
15	8-inch HDPE Leachate Collection Pipe (Perforated, All Inclusive) - Cell 1	LF	1,500	\$101.00	\$151,500.00	
16	8-inch HDPE Leachate Cleanout Pipe, Solid - Cell	EA	1	\$45,000.00	\$45,000.00	

Seminole Rd. Landfill Cell Construction Phase 3, Unit 2; Cell 1 Cell 2 Subgrade



Bid Opening: July 12, 2019

Cost Opening: July 19, 2019

Procurement Agent: Jovan Hooper

				Morgan Corp.	
Item No.	Description	Unit	Estimated Quantity	Unit Price (\$)	Total Amount (\$)
	CELL NO	. 1 & CELL I	NO. 2 SUBGRAD	E	
17	6-inch HDPE Leachate Collection Pipe, Solid - Cell 1	LF	150	\$290.00	\$43,500.0
18	Tie-in to Existing Liner and Leachate Line - Cell 1	LS	1	\$50,000.00	\$50,000.0
19	Temporary Earthen Stormwater Berms (All- inclusive) - Cell 1	LF	950	\$20.00	\$19,000.0
20	Sodding - Cell 1, Leachate Tank Area, & Cell 2	SY	16,000	\$19.35	\$309,600.0
21	Seeding - Cell 1, Leachate Tank Area, & Cell 2	SY	26,600	\$0.95	\$25,270.0
22	Edge of Liner Posts - Cell 1	EA	10	\$300.00	\$3,000.0
23	Site Clearing, Grubbing, and Stripping for Mining area	AC	5.31	\$23,000.00	\$122,130.0
24	Erosion and Sediment Control & Stormwater - Mining Area	LS	1	\$140,000.00	\$140,000.0
25	All-Weather Access Roads	SY	13,800	\$27.80	\$383,640.0
26	Guardrail along Access Road	LF	1,300	\$33.50	\$43,550.0
27	Hauling Soil from Linecrest Mining/Borrow Area	CY	70,800	\$9.90	\$700,920.0
28	Excavate to determine limits of existing underdrain and piping for asbuilt information.	EA	21	\$450.00	\$9,450.0

Seminole Rd. Landfill Cell Construction Phase 3, Unit 2; Cell 1 Cell 2 Subgrade



Bid Opening: July 12, 2019

Cost Opening: July 19, 2019

Procurement Agent: Jovan Hooper

				Morgan Corp.		
Item No.	Description	Unit	Estimated Quantity	Unit Price (\$)	Total Amount (\$)	
	CELL NO). 1 & CELL N	O. 2 SUBGRADE			
29	250,000 Gallon Leachate Storage Tank (52-ft Dia, 17.5-ft Ht), Concrete Secondary Storage Area, Piping, and Valving (All Inclusive)	LS	1	\$1,020,000.00	\$1,020,000.00	
30	Permanent Office Trailer	LS	1	\$175,000.00	\$175,000.00	
31	Removal and Backfill of Unsuitable Materials	CY	5,000	\$10.00	\$50,000.00	
32	Rock Excavation	CY	5,000	\$35.00	\$175,000.00	
33	Demolish Existing Stormwater Pipe	LF	100	\$56.00	\$5,600.00	
34	Removal of Existing Access Road and Stockpiling Stripped Material for Reuse	SY	20,170	\$3.00	\$60,510.00	
	SUBTOTAL BI	D PRICE (Total	of Items 1 Thru 30)	\$13,7	/85,910.92	
		\$80	0,000.00			
	TOTAL BID PRICE (Total of Items 1 Thru 34 plus Contingency)				585,910.92	
TOTAL	L BID PRICE FOR CELL NO. 1 & CELL NO	. 2 SUBGRADE	written in words:			

Recommend Award to Lowest Responsive & Responsible bidder:

Forteen Million, Five Hundres Eighty-Five Thousand, Nine Hundred Ten Dollars and Ninety-Two Cents

Morgan Corporation 1800 East Main Street Duncan, SC 29334

^{*} Awarded Amount is \$13,464,285.92 per BAFO obtained by Morgan Corp. and the acceptance of the BAFO from User Dept.

ITB No. 19-101115

Seminole Rd. Landfill Cell Construction Phase 3, Unit 2; Cell 1 Cell 2 Subgrade



Bid Opening: July 12, 2019

Cost Opening: July 19, 2019

Procurement Agent: Jovan Hooper

			Morgan Corp.				
Item No.	Description	Unit	Estimated Quantity	Unit Price (\$)	Total Amount (\$)		
CELL NO. 1 & CELL NO. 2 SUBGRADE							